

# Haryana Government Gazette Extraordinary

Published by Authority

© Govt. of Haryana

150-2015/Ext.] CHANDIGARH, MONDAY, AUGUST 24, 2015 (BHADRA 2, 1937 SAKA)

# हरियाणा सरकार

नगर तथा ग्राम आयोजना विभाग

# अधिसूचना

दिनांक अगस्त 24, 2015

**संख्या-सी.सी.पी. (एन.सी.आर.) / 2015 / 2463.** -पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41) की धारा 5 की उपधारा (4) द्वारा प्रदान की गई शक्तियों का प्रयोग करते हुए, हरियाणा के राज्यपाल, इसके द्वारा, हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग, अधिसूचना संख्या सी.सी.पी. (एन.सी.आर.) / पी.डबल्यू.एल. / एच.डी.एल. / डी.डी.पी. / 2012 / 2054 दिनांक २७ जून, २०१२, संख्या सी.सी.पी.(एन.सी.आर.) / जे. जे.आर. / डी.डी.पी. / 2012 / 2211 दिनांक 13 जुलाई, 2012, संख्या सी.सी.पी.(एन.सी.आर.) / बी.जी.एच. / एफ.डी.पी. -2031 / 2012 / 2213 दिनांक 13 जुलाई, 2012, संख्या सी.सी.पी.(एन.सी.आर.) / जी.जी.एन.-एफ.जी.आर. / डी.डी.पी. —2031 / 2012 / 2660 दिनांक 21 अगस्त, 2012, संख्या सी.सी.पी.(एन.सी.आर.) / ए.एम.बी. / एफ.डी.पी. / 2012 / 2916 दिनांक 6 सितम्बर, २०१२, संख्या सी.सी.पी.(एन.सी.आर.) / एफ.डी.पी.—२०३१ / जी.जी.एन. / २०१२ / ३५४१ दिनांक १५ नवम्बर, २०१२, संख्या सी.सी.पी.(एन.सी.आर.) / एफ.डी.पी.—2031 / जी.जी.एन.—एस.एच.एन. / 2012 / 3543 दिनांक 15 नवम्बर, 2012, संख्या सी.सी.पी. (एन.सी.आर.) / आर.टी.के. / डी.डी.पी.–के.एल.एन.–2031 / 2013 / 67 दिनांक 7 जनवरी. 2013. (एन.सी.आर.) / आर.टी.के. / डी.डी.पी.—2031 / 2013 / 69 दिनांक 7 जनवरी, 2013, सी.सी.पी.(एन.सी.आर.) / एफ.डी.पी. / (पी.के.एल.—11 / ए.पी.आर.) / 2013 / 147, दिनांक 11 जनवरी, 2013, संख्या सी.सी.पी.(एन.सी.आर.)जी.जी.एन. / एफ.डी.पी—2031 / पी.टी.डी—एच.एम.डी. / 2013 / 308, दिनांक 28 जनवरी, 2013, संख्या सी.सी.पी.(एन.सी.आर.) / के.एन.एल. /एफ.डी.पी. / 2013 / 2199, दिनांक 2 सितम्बर, संख्या सी.सी.पी.(एन.सी.आर.) / के.के.आर-1 / डी.डी.पी. 2013. -2031 / 2014 / 6 दिनांक 2 जनवरी, 2014, संख्या सी.सी.पी.(एन.सी.आर.) / डी.डी.पी. / बेरी-2031 / 2014 / 10 दिनांक 2 जनवरी, 2014, संख्या सी.सी.पी.(एन.सी.आर.) / डी.डी.पी. / के.टी.एल. / के.सी.ए. / 2014 / 360 दिनांक 21 फरवरी, 2014, संख्या सी.सी.पी.(एन.सी.आर.) / एफ.बी.सी.(डी.डी.पी.—31) / 2014 / 1312 दिनांक 14 जुलाई, 2014, में प्रकाशित अंचल विनियमों में संशोधन का निम्नलिखित प्रारूप उन सभी व्यक्तियों की जानकारी के लिए प्रकाशित करते हैं जिनके इससे प्रभावित होने की संभावना है।

इसके द्वारा, नोटिस दिया जाता है कि इस अधिसूचना के राजपत्र में प्रकाशन की तिथि से तीस दिन की अवधि की समाप्ति पर अथवा इसके पश्चात् सरकार, संशोधन प्रारूप पर ऐसे आक्षेपों अथवा सुझावों सिहत, यदि कोई हो, जो निदेशक, नगर तथा ग्राम आयोजना, हरियाणा, एस.सी.ओ. संख्या 71–75 (द्वितीय से तृतीय तल), सैक्टर–17 सी, चण्डीगढ़, द्वारा लिखित रूप में किसी व्यक्ति से संशोधन प्रारूप के संबंध में विनिर्दिष्ट अवधि की समाप्ति से पूर्व, प्राप्त किये जाएं, पर विचार करेगी।

Price: Rs. 5.00 (2109)

#### संशोधन प्रारूप

हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग, अधिसूचना संख्या– संख्या सी.सी.पी.(एन.सी.आर.) / पी.डबल्यू.एल. /एच.डी.एल./डी.डी.पी./2012/2054 दिनांक 27 जून, 2012, संख्या सी.सी.पी.(एन.सी.आर.)/जे.जे.आर./डी.डी.पी. /2012/2211 दिनांक 13 जुलाई, 2012, संख्या सी.सी.पी.(एन.सी.आर.)/बी.जी.एच./एफ.डी.पी.—2031/2012/2213, दिनांक 13 जुलाई, 2012, संख्या सी.सी.पी.(एन.सी.आर.) / जी.जी.एन.-एफ.जी.आर. / डी.डी.पी.-2031 / 2012 / 2660 दिनांक 21 अगस्त, 2012, संख्या सी.सी.पी.(एन.सी.आर.) / ए.एम.बी. / एफ.डी.पी. / 2012 / 2916 दिनांक 6 सितम्बर, 2012, संख्या सी.सी.पी.(एन.सी. आर.) / एफ.डी.पी. – 2031 / जी.जी.एन. / 2012 / 3541 दिनांक 15 नवम्बर, 2012, संख्या सी.सी.पी.(एन.सी.आर.) / एफ.डी.पी. —2031 / जी.जी.एन.—एस.एच.एन. / 2012 / 3543, दिनांक १५ नवम्बर, २०१२, संख्या सी.सी.पी.(एन.सी.आर.) / आर.टी.के. / डी.डी. पी. – के. एल. एन. – 2031 / 2013 / 67 दिनांक 7 जनवरी, 2013, संख्या सी.सी.पी.(एन.सी.आर.) / आर.टी.के. / डी.डी.पी. —2031 / 2013 / 69 दिनांक ७ जनवरी, 2013, संख्या सी.सी.पी.(एन.सी.आर.) / एफ.डी.पी. / (पी.के.एल.−11 / ए.पी.आर.) / 2013 / 147, दिनांक 11 जनवरी, 2013, संख्या सी.सी.पी.(एन.सी.आर.)जी.जी.एन. / एफ.डी.पी—2031 / पी.टी.डी—एच.एम.डी. / 2013 / 308, दिनांक 28 जनवरी, 2013, संख्या सी.सी.पी.(एन.सी.आर.) / के.एन.एल. / एफ.डी.पी. / 2013 / 2199, दिनांक 2 सितम्बर, 2013, संख्या सी.सी.पी.(एन.सी.आर.) / के.के.आर-1 / डी.डी.पी.-2031 / 2014 / 6 दिनांक 2 जनवरी, 2014, संख्या सी.सी.पी.(एन.सी.आर.) / डी.डी.पी. / बेरी-2031 / 2014 / 10 दिनांक 2 जनवरी, 2014, संख्या सी.सी.पी.(एन.सी.आर.) / डी.डी.पी. / के.टी.एल. / के.सी.ए. / 2014 / 360 दिनांक 21 फरवरी, 2014, संख्या सी.सी.पी.(एन.सी.आर.) / एफ.बी.सी. (डी.डी.पी. -31)/2014/1312 दिनांक 14 जुलाई, 2014, के परिशिष्ट "ख" में अनुबन्ध "ख" में अंचल विनियम में, "IV परिवहन तथा संचार अंचल" शीर्ष के नीचे अंत में निम्नलिखित जोड दिया जायेगा अर्थात:-

"वेयरहाउस, सैक्टर के कुल क्षेत्र के 5 प्रतिशत की अधिकतम सीमा तक। सरकार द्वारा विनिश्चित की गई नीति / पैरामीटर्स के अनुसार।"

पी. राघवेन्द्र राव,

अपर मुख्य सचिव, हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग।

#### HARYANA GOVERNMENT

#### TOWN AND COUNTRY PLANNING DEPARTMENT

# Notification

The 24th August, 2015

No. CCP (NCR) / 2015/2463.— In exercise of the powers conferred by Sub-section (4) of Section 5 of the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963), the Governor of Haryana hereby publishes the following draft of amendment in the Haryana Government, Town and Country Planning Department Notifications No. CCP(NCR)/PWL/HDL/DDP/2012/2054 dated the 27th June, 2012, No. CCP(NCR)/JJR/DDP/2012/2211 dated the 13th July, 2012, No. CCP(NCR)/BGH/FDP-2031/2012/2213 dated the 13th July, 2012, No. CCP(NCR)/GGN-FGR/DDP-2031/2012/2660 dated the 21st August, 2012, No.CCP(NCR)/AMB/FDP/2012/2916 dated the 6th September, 2012, No. CCP(NCR)/FDP-2031/GGN/2012/3541 dated the 15th November, 2012, No. CCP(NCR)/FDP-2031/GGN-SHN/2012/3543 dated the 15th November, 2012, No. CCP(NCR)/RTK/DDP-KLN-2031/2013/67 dated the 7th January, 2013, No. CCP(NCR)/RTK/DDP-2031/2013/69 dated the 7th January, 2013, No. CCP(NCR)/FDP/(PKL-11/APR)/2013/147 dated 11th January, 2013, No. CCP(NCR)/GGN/FDP-2031/PTD-HMD/2013/308 dated the 28th January, 2013, No. CCP(NCR)/KNL/FDP/2013/2199 dated the 2nd September, 2013, No. CCP(NCR)/KKR-1/DDP-2031/2014/6 dated the 2nd January, 2014, No. CCP(NCR)/DDP/BERI-2031/2014/10 dated the 2nd January, 2014, No. CCP(NCR)/DDP/STL/KCA/2014/360 dated the 21st February, 2014, No. CCP(NCR)/FBC(DDP-31)/2014/1312 dated the 14th July, 2014, in the zoning regulations for the information of persons likely to be affected thereby.

Notice is hereby given that the draft of amendment shall be taken into consideration by the Government on or after the expiry of a period of thirty days from the date of publication of this notification in the Official Gazette together with any objection or suggestions, if any, which may be received in writing by the Director, Town and

Country Planning, Haryana, S.C.O. No 71-75 (Second to Third Floor), Sector-17 C, Chandigarh, from any person with respect to the draft of the amendment, before the expiry of the period so specified.

#### DRAFT AMENDMENT

In the Haryana Government, Town and Country Planning Department, Notifications No. CCP(NCR)/PWL/HDL/DDP/2012/2054 dated the 27th June, 2012, No. CCP(NCR)/JJR/DDP/2012/2211 dated the 13th July, 2012, No. CCP(NCR)/BGH/FDP-2031/2012/2213 dated the 13th July, 2012, No. CCP(NCR)/GGN-FGR/DDP-2031/2012/2660 dated the 21st August, 2012, No. CCP(NCR)/AMB/FDP/2012/2916 dated the 6th September, 2012, No. CCP(NCR)/FDP-2031/GGN/2012/3541 dated the 15th November, 2012, No. CCP(NCR)/FDP-2031/GGN-SHN/2012/3543 dated the 15th November, 2012, No. CCP(NCR)/RTK/DDP-KLN-2031/2013/67 dated the 7th January, 2013, No. CCP(NCR) / RTK / DDP-2031 / 2013/69 dated the 7th January, 2013, No. CCP(NCR)/FDP/(PKL-11/APR)/2013/147 dated 11th January, 2013, No. CCP(NCR)/GGN/FDP-2031/PTD-HMD/2013/308 dated the 28th January, 2013, No. CCP(NCR)/KNL/FDP/2013/2199 dated the 2nd September, 2013, No. CCP(NCR)/KKR-1/DDP-2031/2014/6 dated the 2nd January, 2014, No. CCP(NCR)/DDP/BERI-2031/2014/10 dated the 2nd January, 2014, No. CCP(NCR)/FBC(DDP-31)/2014/1312 dated the 14th July, 2014, in Annexure 'B', in Appendix 'B' in the Zoning Regulations under heading "IV Transport and Communication Zone" in the end the following shall be added, namely:-

"Warehouses upto a maximum limit of 5% of the total area of the sector.

As per policy/parameters decided by the Government."

P. RAGHAVENDRA RAO, Additional Chief Secretary to Government, Haryana, Town and Country Planning Department.

#### हरियाणा सरकार

नगर तथा ग्राम आयोजना विभाग

# अधिसूचना

दिनांक 24 अगस्त, 2015

संख्या सी0सी0पी0 (एन.सी.आर) / डी.डी.पी. (आद बद्री) /2015/2461 .—पंजाब अनुसूचित सड़कें तथा नियन्त्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41), की धारा 5 की उपधारा (4) द्वारा प्रदत्त शिक्तयों का प्रयोग करते हुए, हरियाणा के राज्यपाल, इसके द्वारा, अनुबंध 'ख' में विर्निदिष्ट नियन्त्रित क्षेत्रों को लागू किए जाने वाले प्रस्तावित अनुबंध क तथा ख में दिए गए निर्बन्धनों तथा शर्तों सिहत हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग, अधिसूचना संख्या सी0सी0पी0 (एन.सी.आर) 2003/वाई एन-IV/1791, दिनांक 18 अगस्त,2003 तीर्थ आद बद्री, जिला यमुनानगर के इर्दगिर्द के नियन्त्रित क्षेत्र के लिए प्रारूप विकास योजना, 2031 ए0डी0 प्रकाशित करते हैं।

इसके द्वारा, नोटिस दिया जाता है कि इस अधिसूचना के राजपत्र में प्रकाशन की तिथि से तीस दिन की अविध की समाप्ति पर अथवा इसके पश्चात् सरकार, प्रारूप विकास योजना पर, आक्षेपों अथवा सुझावों सिहत, यदि कोई हो, जो निदेशक, नगर तथा ग्राम आयोजना विभाग, हिरयाणा, एस.सी.ओ. 71—75 (पहली से तीसरी मंजिल) सैक्टर—17 सी, चण्डीगढ़ द्वारा, इस प्रारूप विकास योजना के संबंध में लिखित में किसी व्यक्ति से इस प्रकार विनिर्दिष्ट अविध की समाप्ति से पूर्व प्राप्त किए जाएं, विचार करेगी।

# ड्राईंग

- 1. विद्यमान भूमि उपयोग योजना ड्राईंग संख्या डी.टी.पी.(वाई) 150 / 03, दिनांक 15 अप्रैल, 2003.
- 2. प्रारूप विकास योजना 2031ए.डी., आद बद्री ड्राईंग संख्या डी.टी.पी.(वाई)/316/2014 दिनांक 5 जुलाई, 2014.

# अनुबन्ध-क

तीर्थ आद बद्री, जिला यमुनानगर के इर्द गिर्द घोषित नियन्त्रित क्षेत्र की प्रारूप विकास योजना—2031 ए.डी. पर व्याख्यात्मक टिप्पणी

# 1. परिचयः

आद बद्री एक प्राचीन हिन्दु तीर्थ स्थल है। भगवान विष्णु (बद्री नारायण) तथा देवी लक्ष्मी का एक प्राचीन मन्दिर समुद्र तल से लगभग 455 मीटर ऊँची पहाड़ की चोटी पर स्थित है। वैदिक समय की पवित्र नदी सरस्वती (अब लुप्त) का उद्गम स्थल भी तीर्थ मन्दिर के निकट ही स्थित है। भारतीय पुरातत्व सर्वेक्षण को आद बद्री तथा इसके आस पास के क्षेत्र में प्राचीन सभ्यता के अवशेष प्राप्त हुए हैं। मन्दिर के निकट भगवान शिव, भगवान गणेश तथा देवी पार्वती की नोवी तथा दसवीं शताब्दी तथा 11 वीं तथा 12 वीं शताब्दी की महात्मा बुद्ध की मुर्तियां भी पूजास्थल के पास प्राप्त हुई हैं। पर्यटन सम्भावनाओं तथा धार्मिक भावनाओं के कारण यह स्थान महत्त्वपूर्ण बनता जा रहा है। कपाल मोचन के मेले के दौरान लाखों श्रद्धालु यहां आते हैं।

#### 2. स्थिति, प्रादेशिक संस्थापन तथा जलवाय्

तीर्थ आद बद्री यमुनानगर से लगभग 42 किलो मीटर तथा बिलासपुर से इसके उत्तर की ओर लगभग 18 किलोमीटर की दूरी पर स्थित है। गाँव जोड़क मार्ग (रणजीत पुर—काठगढ़ मार्ग ) इस स्थान को बिलासपुर —धनौरा मार्ग से जोड़ता है। मन्दिर शिवालिक श्रृंखला की कम ऊचाई वाली पहाड़ी पर हिमाचल प्रदेश की सीमा के नजदीक समुद्र तल से लगभग 455 मीटर की ऊंचाई पर स्थित है। वार्षिक औसत वर्षा लगभग 1250 मिली मीटर है। भू—गत जल लगभग 50 फुट गहरा है, इसका पी.एच. मुल्यांकन 7.5 से 8 तक है, जोकि फसलों तथा पीने के उद्देश्य हेतू अच्छा है। मिट्टी रेतीली दोमट (चिकनी मिट्टी के कणों सहित) है, जोकि कृषि के लिए उपयुक्त समझी जाती है।

# 3. नियन्त्रित क्षेत्र घोषित करने की आवश्यकता

आद बद्री तीर्थ न केवल एक प्राचीन तीर्थ स्थल है बल्कि एक अत्यन्त महत्वपूर्ण पुरातत्व स्थल भी है। ऐसा विश्वास है कि प्राचीन सरस्वती नदी, जो अब लुप्त हो चुकी है, का उद्गम स्थल यही है। केन्द्रीय सरकार ने एक संग्राहलय का निर्माण करने तथा भारतीय पुरातत्व सर्वेक्षण द्वारा खुदाई के कार्य हेतू धन राशि प्रदान की है। आद बद्री एवं इसके आस पास के क्षेत्र में पुरानी सभ्यता के अंश प्राप्त हुए हैं। तीर्थ यात्रियों की संख्या हर वर्ष बढ़ रही है। इस पवित्र स्थान अधीन परिदृश्य के चलते अव्यवस्थित विकास का रोका जाना तथा नियोजित विकास सुनिश्चित किया जाना आवश्यक था। इसे ध्यान में रखते हुए मन्दिर के इर्द गिर्द हरियाणा सराकार के राजपत्र दिनांक 26 अगस्त, 2003 में प्रकाशित हरियाणा सरकार, अधिसूचना संख्या सी.सी.पी.(एन.सी.आर)/2003/वाई एन. VI/1791, दिनांक 18 अगस्त, 2003 द्वारा नियन्त्रित क्षेत्र घोषित किया गया है।

# 4. भूमि उपयोग की प्रस्तावना

मुख्यतः इस धार्मिक जगह की पवित्रता और महत्ता को बनाये रखने के लिये ही नियन्त्रित क्षेत्र घोषित कराया गया है। इसी के मध्यनजर, जनसंख्या प्रक्षेपित नहीं की गई है। परिणामतः प्रारूप विकास योजना में कोई शहरीकरण की प्रस्तावना नहीं बनाई गई है। पूरे नियन्त्रित क्षेत्र को भिन्न— भिन्न जोन में उनके भूमि उपयोग को दर्शाते हुए विभक्त किया गया है। विभिन्न प्रस्तावित भू—उपयोगों का वर्गीकरण नीचे सारणी में दर्शाया गया है।

# भूमि उपयोगों का वितरण

क्रम संख्या	भूमि उपयोग का नाम	क्षेत्र (हैक्टेयर में)	कुल क्षेत्र का प्रतिशत
1	परिवहन तथा संचार	13.64	6.88
2	जन उपयोग अंचल	10.57	5.33
3	खुला क्षेत्र	63.13	31.84
4	विशेष अंचल	20.53	10.35
5	प्रतिबंधित अंचल	90.41	40.60
	कुल	198.48	100.00

भू-उपयोगों की संक्षिप्त व्याख्या निम्न प्रकार से है:-

#### (i) परिवहन तथा संचार

शहरीकरण प्रस्तावना न होने के कारण वाहनों और पैदल ट्रैफिक का घनत्व, कपाल मोचन मेला के दिनों के इलावा बहुत अधिक रहने की उम्मीद नहीं है। अतः मुख्य मार्ग प्रणाली की प्रस्तावना नहीं की गई है। लेकिन इस स्थान के महत्व को ध्यान में रखते हुए मौजूदा मार्ग प्रणाली को सुदृढ़ करने की आवश्यकता है। इस बारे निम्न प्रस्तावनाएं की गई हैं:—

- मुख्य अंचल जोन में 5 एकड़ भूमि बस स्टैंड हेतू निर्धारित की गई है।
- मौजूदा रणजीत पुर—काठगढ़—आद बद्री सड़क को मैदानी क्षेत्र में 30 मीटर और पहाड़ी भूमि प्रदेश में 15 मीटर चौडा किया जाना।
- सोम्ब नदी के पूर्वी किनारे पर पुरातत्त्व स्थल को जोड़ने हेतू दो पुल की प्रस्तावना।
- सोम्ब नदी के पूर्वी किनारे पर पैदल चलने वालों के लिये 15 मीटर चौडी पगडंडी।
- दो रास्ते आम जनता के द्वारा बनाऐ गऐ है। पहला आद बद्री और माता मन्तरा देवी मन्दिर तक और दूसरा प्रस्तावित 5 मीटर चौड़ी मार्ग से माता मन्तरा देवी मन्दिर तक। तथापि, दोनों रास्ते राजस्व रिकार्ड में दर्शाए नहीं गए हैं। इन रास्तों की चौडाई 5 फीट से 10 फीट है जोकि 5 मीटर चौडा किया जाना प्रस्तावित हैं।

इस उपयोग के अधीन कुल 13.64 हैक्टेयर भूमि का निर्धारण किया गया है।

# (ii) जन उपयोगिताएं

जन उपयोगिताओं, उदाहरणार्थः जलघर, बिजली उपघर, ठोस कचरा प्रबन्धन, मल तथा जल निकासी प्रस्थापना स्थलों के समायोजन हेतू 10.57 हैक्टेयर क्षेत्र को चिन्हित किया गया है। 5 हैक्टेयर भूमि सिवरेज ट्रीटमैंट प्लांट हेतू नियन्त्रित क्षेत्र से बाहर सोम्ब नदी के किनारे पर निर्धारित की गई है।

#### (iii) खुले क्षेत्र

इस स्थान की शान्ति, स्वच्छता तथा स्वास्थयवर्धक वातावरण को बनाए रखने के उद्देश्य, पार्क विकसित करने तथा अन्य मनोरंजनात्मक उपयोगों के हेतू 63.3 हैकटेयर भूमि इस प्रयोगों के अधीन निर्धारित की गयी है।

#### (iv) विशेष अंचल

इस जगह के धार्मिक चरित्र को मध्य नजर रखते हुए 20.53 हैक्टेयर भूमि विशेष अंचल के उपबन्धों हेतू निर्धारित की गई है। इसमें संस्थाएं, कार्यालय, मनोरंजनात्मक भवन तथा उपरोक्त वर्णित मुख्य प्रयोगों के अन्तर्गत रिहायशी, वाणिज्यिक तथा किसी अन्य कार्य हेतू क्षेत्र शामिल होंगे।

# (v) प्रतिबन्धित अंचल

सोम नदी के दोनो ओर पुरातत्व विभाग के स्थलों के आस पास की 90.41 हैक्टेयर भूमि को प्रतिबन्धित अंचल प्रस्तावित किया गया है। वन विभाग की अधिसूचना के अनुरूपता प्रतिबन्धित अंचल की सीमा को निश्चित किया जाएगा। इस अंचल में किसी भी प्रकार के निर्माण के क्रिया क्लाप की अनमित नहीं दी जायेगी लेकिन मन्दिर, संग्राहालय, विश्राम गृह पुलिस पोस्ट का निर्माण अथवा पुनः निर्माण तथा क्षेत्र के पर्यावरण सुधार तथा सुन्दरता के लिए अन्य आवश्यक विकास कार्य किये जा सकेंगे।

# (vi) सुरक्षात्मक वन क्षेत्र

कुल भूमि क्षेत्र के 2/3rd बारे में एक क्षेत्र संरक्षित वन क्षेत्र के रूप में आरक्षित है। क्षेत्र के सौर्न्दयकरण तथा पर्यावरण सुधार अन्य जरूरी विकास कार्यों के अलावा, इस क्षेत्र में कोई निर्माण क्रिया क्लाप की अनुमति नहीं दी जाएगी।

# (vii) कृषि अंचल

विभिन्न उपयोगों के अधीन प्रस्तावित शेष नियन्त्रित क्षेत्र को कृषि अंचल हेतू आरक्षित करना प्रस्तावित है। तथापि इस क्षेत्र में आवश्यक भवन विकास का विलोपन नहीं होगा जैसा कि आबादी देह के साथ लगते मौजूदा गांवों का विस्तार, यदि सरकार द्वारा अनुमोदित प्रायोजना के उत्तरदायित्व के रूप में शुरू किया गया हो या प्रायोजित हो तथा कृषि भूमि के रखरखाव तथा सुधार हेतू आवश्यक सुविधाओं के अन्य विस्तार को समाप्त नहीं करेगा।

# 5. अंचल विनियमः

भूमि उपयोग सबंधी प्रस्तावों को नियमित अंचल विनियमों द्वारा विधि पवित्रता जो इस विकास योजना का भाग है, वैध है। ये विनियम भूमि उपयोग में परिवर्तन और विकास मानकों के लिये लागू होंगे। इन विनियमों में विभिन्न मुख्य भूमि उपयोगों में अनुमत सम्बन्ध तथा सहायक उपयोगों का भी बहुत विस्तारपूर्वक वर्णन किया गया है और यह तय किया गया है कि भूमि उपयोग परिवर्तन तथा विकास, योजना में दिये गये ब्यौरे अनुसार होगा। इससे प्रत्येक सेक्टर का निर्दिष्ट विकास और उचित नियन्त्रण करने हेतु विस्तृत सेक्टर योजनायें तैयार किया जाना संम्भव हो सकेगा। नियमित अंचल विनियमों द्वारा भूमि उपयोग सम्बन्धी प्रस्तावों की जो इस विकास योजना का भाग है, के प्रभाव को विधि पवित्रता दी जा रही है।

# अनुबन्ध ख

#### अंचल विनियमः

आद बद्री के चारों तरफ के नियन्त्रित क्षेत्र शासकीय प्रयोग तथा विकास में आने वाली भूमि की ड्राईंग संख्या डी.टी. पी(वाई) 316/2014, दिनांक 05 जुलाई, 2014 में दर्शाये गये अनुसार है।

#### I. सामान्यः

- 1. आद बद्री के इर्द गिर्द नियन्त्रित क्षेत्र के लिए विकास योजना का भाग बनने वाले, इन अंचल विनियमों को आद बद्री के नियंन्त्रित क्षेत्रों के लिये विकास योजना का प्रारूप अंचल विनियम कहा जाएगा।
- 2. इन विनियमों की आवश्यकता प्रारूप विकास योजना द्वारा सम्पूर्ण आवृति क्षेत्र के विस्तार के लिए होगा तथा पंजाब अनुसूचित सड़कें तथा नियंन्त्रित क्षेत्र नियमित विकास निर्बन्धन अधिनियम 1963 (1963 का पंजाब अधिनियम 41) तथा उसके अधीन बनाये गये नियमों की आवश्यकता के अतिरिक्त होगीं।

# II. परिभाषाएं

#### इन विनियमों में :--

- (क) ''अनुमोदित'' से अभिप्राय है नियमों के अधीन अनुमोदित;
- (ख) ''भवन नियमों'' से अभिप्राय हैं, नियमों के भाग–VII में निहित नियम;
- (ग) "ड्राइंग" से अभिप्राय है, ड्राइंग संख्या—डी.टी.पी. (वाई)—316/2014, दिनांक 05 जुलाई, 2014.
- (घ) ''फर्श क्षेत्र अनुपात (फ0क्षे0अनु0)'' से अभिप्राय है, किसी भवन की सभी मंजिलों के कुल फर्श और स्थल के कुल क्षेत्र के बीच प्रतिशतता में दर्शाया गया अनुपातम ;
- (ङ) ''फार्म गृह'' से अभिप्राय है, किसी फार्म के स्वामी द्वारा अपनी भूमि पर निम्नलिखित प्रयोजनार्थ निर्मित घर है—
  - (i) निवास यूनिट अर्थात् मुख्य उपयोगः; तथा
  - (ii) फार्म छायाबान अर्थात् गौण उपयोगः

# टिप्पणी:

- (i) फार्म गृह का निर्माण ''कृषि अंचल में आबादी से बाहर फार्म गृहों की व्यवस्था'' संबंधी खण्ड XIX के अधीन दिये गये निर्बन्धनों से शासित होगा; तथा
- (ii) फार्म शैड, "भवन नियंत्रण और स्थल विशिष्टियों" संबंधी खंड XIX में उल्लिखत निर्बन्धनों द्वारा शासित होंगे;
- (च) "हरित पट्टी" से अभिप्राय है, विकास योजना में दर्शाय गये सैक्टर/मुख्य सड़क के साथ—साथ भूमि की पट्टियां जो मुखयतः भविष्य में इन सड़कों को चौड़ा करने अथवा आवश्यक सेवाएं उपलब्ध कराने हेतु होंगी;
- (छ) ''अटारी'' से अभिप्राय है, सामान्य फर्श से ऊपर अधिकतम 1.5 मीटर की ऊँचाई ढलुआ छत में शेष बचे स्थान पर मध्यवर्ती फर्श, जो भंडारण प्रयोजन हेतू निर्मित करवाई जाती है अथवा अपना ली जाती है;
- (ज) ''वास्तविक तिथि'' से अभिप्राय है, नीचे वर्णित नियन्त्रित क्षेत्रों की अधिसूचनाओं की हरियाणा राजपत्र में प्रकाशन की तिथि

क्रम संख्या	नियंत्रित क्षेत्र का नाम तथा अधिसूचना संख्या	वस्तविक तिथि
1	आद बद्री में घोषित नियंत्रित क्षेत्र, अधिसूचना संख्या सी.सी.पी.(एन.सी.आर.) २००३ / वाई.एन.—VI/1791, दिनांक 18 अगस्त, २००३	26 अगस्त, 2003

- (झ) ''परछती तल'' का अभिप्राय है, भूतल के ऊपर मध्यवर्ती तल जिसमें परछती उस तल के क्षेत्रफल का 1/3 तक सीमित होती है तथा जिसमें भूमि की सतह से ऊपर कम से कम 2.2 मीटर ऊँचाई हो ;
- (ञ) नियंत्रित क्षेत्र में किसी भूमि अथवा भवन के संबंध में ''अननुरूप उपयोग'' से अभिप्राय है, ऐसी भूमि अथवा भवन का वर्तमान उपयोग जो विकास योजना में क्षेत्र के उस भाग के लिए निर्दिष्ट मुख्य भूमि उपयोग के विपरीत हो;
- (ट) ''सार्वजनिक उपयोगिता सेवा भवन'' से अभिप्राय है, ऐसा भवन जो सार्वजनिक उपयोगिता सेवाओं के लिए अपेक्षित हो, जैसा जल सप्लाई, जल निकास, बिजली, डाक तथा तार एवं परिवहन तथा दमकल केन्द्र सहित कोई नगरपालिका सेवा ;
- (ठ) 'नियमों' से अभिप्राय है, पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन नियम, 1965 ;
- (ड) 'स्थल आच्छादन' से अभिप्राय है, भवन के भूतल पर नियमित क्षेत्र और स्थल के बीच प्रतिशतता द्वारा दर्शाया गया अनुपात ;
- (ढ) ''कृषि उपयोग साधन'' से अभिप्राय होगा, ऐसा विकास तथा गतिविधियां, जो कृषि संबंधी कार्यों को करने में सहायक रूप में अपेक्षित है, जैसे कि नलकूप, पम्प, चैम्बर, वायु चक्की, सिंचाई नाले, पक्के प्लेटफार्म, बाड़ लगाना तथा अधिकतम चार फुट ऊँची चारदीवारी बनाना जिसके ऊपर अधिकतम तीन फुट ऊँची बाड़ हो, जल नलके आदि :
- (ण) ''अधिनियम'', ''कालोनी'', ''उप—िनवेशक'', ''विकास योजना'', ''सैक्टर'' और ''सैक्टर योजना'' शब्दों का वहीं अर्थ होगा जो उन्हें पंजाब अनुसूचित सड़कें तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का अधिनियम 41) और नियम 1965 में उनको दिया गया है ; तथा
- (त) अन्य शब्दों का वही अर्थ होगा, जो उन्हें पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का अधिनियम 41) में दिया गया है ।

# III. मुख्य भूमि उपयोग अंचल

- (i) परिवहन तथा संचार
- (ii) जन उपयोगिताएं
- (iii) खुले स्थान अंचल
- (iv) विशेष अंचल
- (v) प्रतिबंधित अंचल

मुख्य भूमि का वर्गीकरण परिशिष्ट 'क' के अनुसार है।

# IV. सैक्टरों में विभाजन :-

उपर्युक्त अंचल विनियमन III में क्रम संख्या (i) से (v) पर वर्णित भूमि उपयोग जो भवन परियोजनार्थ भूमि उपयोग है उन्हें दर्शाये अनुसार सैक्टरों में विभाजित किया गया है। प्रत्येक सैक्टर के ड्राईंग में दिखाये अनुसार एक निश्चित संख्या दी गई है।

# v. मुख्य उपयोगों में भूमि उपयोग सम्बन्धी ब्यौरे :-

मुख्य, सहायक तथा गौण उपयोग के लिए इन विनियमों तथा नियमों को अन्य उपेक्षाओं के अध्यधीन सम्बन्धित मुख्य भूमि उपयोग अंचल में अनुमित दी जा सकती है उनकी सूची परिशिष्ट 'ख' पर दी गई है जो इन अंचल विनियमों के साथ जोड़े गए हैं।

# VI. विकास के लिए अपूर्ण विकसित सैक्टर :-

विभिन्न सैक्टरों में भवन प्रयोजनों संबंधित भूमि उपयोग के लिए आरक्षण होने पर भी निदेशक, नियंत्रित क्षेत्र के सघन तथा आर्थिक विकास के दृष्टिगत किसी प्रकार के परिवर्तन के लिए अथवा उस पर किसी भवन के निर्माण के लिए अनुमित तब तक नहीं देगा जब तक जल वितरण जलमल विकास व्यवस्था तथा अन्य सुविधाएं, इन सैक्टरों में, उसकी तसल्ली तक सुनिश्चित रूप में उपलब्ध नहीं हो जाती है।

# VII. मुख्य सड़कों के लिए भूमि आरक्षण :-

(1) ड्राईंग में चिन्हित की गई मुख्य सड़कों के लिए भूमि का आरक्षण निम्न प्रकार से किया जाएगा ।

क्रमांक	वर्गीकरण	सड़कें	आरक्षित भूमि
1	वी—1 (ए)	वर्तमान रणजीतपुर—काठगढ़श्आद बद्री मार्ग।	दोनो तरफ 30 मीटर चौड़ी हरित पट्टी सहित ए से लेकर ए1 तक 30 मीटर चौड़ी तथा ए1 से ए2 तक 15 मीटर चौड़ी की जानी है।
2	वी—1 (बी)	वर्तमान काठगढ़ से रामपुर गैन्दा।	30 मीटर तक चौड़ा किया जाना हैं।

(2) अन्य सड़कों की चौड़ाई तथा सीधाई सैक्टर योजना के अनुसार या कालोनियों की अनुमोदित अभिविन्यास योजना के अनुसार होगी।

# VIII. विद्यमान या भूमि उपयोग में वैद्य परिवर्तन की अनुमति प्राप्त अननुरूप उपयोग :--

- (1.) विकास योजना में अनुरूप अंचल से भिन्न अंचल में दिखाई गई विद्यमान परियोजनाओं के सम्बन्ध में निदेशक द्वारा निर्धारित की जाने वाली नियत अविध के लिए अननुरूप उपयोग जारी रखने की अनुमित दी जा सकती है। किन्तू ये अविध दस वर्ष से अधिक नहीं होगी बशर्ते कि सम्बद्ध भवन उद्योग स्वामी :--
  - (क) निदेशक द्वारा यथा निर्धारित किये गये स्थल के बाह्य विकास के लिए निर्धारित अनुपातिक प्रभारों को, जब भी निदेशक द्वारा इस बारे में चाहा जाए अदा करने का वचन देता है;
  - (ख) अंतरिम अवधि के दौरान निदेशक की संतुष्टि के अनुसार मल निकास के लिए संतोषजनक व्यवस्था करता है; तथा
  - (ग) अननुरूप उपयोग के क्षेत्र में किसी प्रकार के विस्तार की अनुमति नहीं होगी।
- (2.) भूमि उपयोग अनुमित के वैध परिवर्तन वाली परियोजना तथा विकास योजना में अनुरुप—उपयोग अंचल से भिन्न अंचलों में स्थित परियोजनाओं के सम्बन्ध में, ऐसे अननुरुप उपयोग जारी रखने की अनुमित दी जाएगी, बशर्ते की सम्बद्ध भवन का स्वामी :—
  - (क) निदेशक द्वारा किये गये यथा निर्धारित स्थल के वाह्य विकास के लिए जब कभी निदेशक द्वारा इस बारे में चाहा जाए अदा करने का वचन देता है; तथा
  - (ख) अंतरिम अवधि के दौरान निदेशक की सन्तुष्टि के अनुसार मल निकास के लिए सन्तोषजनक व्यवस्था करता है।

# IX. अननुरूप उपयोग बन्द करना :-

- (1) यदि किसी भूमि का अननुरूप उपयोग दो वर्ष या इससे अधिक अवधि के लिए लगातार बन्द रहा हो, तो उसे समाप्त हुआ समझा जाएगा और अनुमत उपयोग के अनुसार ही भूमि के पुनः उपयोग या पुनः विकास की अनुमति दी जाएगी।
- (2) यदि अननुरूप उपयोग भवन, आग, बाढ़, विस्फोट, भूकम्प, लड़ाई, दंगा या किसी अन्य प्राकृतिक आपदा से पुनः उत्पादन मूल्य के 50 प्रतिशत या इससे अधिक क्षतिग्रस्त हो जाता है तो उसे केवल अनुमत उपयोग के लिए पुनः विकसित करने की अनुमति दी जाएगी।
- (3) खण्ड IX के अधीन नियत अविध के समाप्त होने के बाद ऐसी भूमि केवल अनुमत उपयोग के पुनः विकसित करने या उपयोग में लाने की अनुमति दी जाएगी।
- (4) खण्ड IX (1) के अधीन नियत अवधि की समाप्ति के बाद भूमि केवल अनुरूप प्रयोग के लिए पुनः उपयोग की अनुमति दी जायेगी।
- X. सैक्टर योजना तथा आंचलिक योजना के अनुरूप विकास :— विनियम IX में दिये गये प्रावधान को छोड़कर कोई मुख्य भूमि उपयोग जिसमें भूमि विधमान है को भवन निर्माण परियोजनार्थ उपयोग और विकसित करने की अनुमित नहीं दी जायेगी जब तक कि प्रस्तावित उपयोग और विकास सैक्टर योजना और आंचलिक योजना अथवा अनुमोदित कालोनी योजना से दिखाये गए ब्यौरे के अनुसार न हो।
- XI. अनुमोदित अभिन्यास या जोनिंग योजना का भाग बनने वाले अलग —अलग स्थलः—प्लाट पर भवन के निर्माण या पुनः निर्माण की अनुमित तब तक नहीं दी जाएगी जब तक कि—
  - (i) प्लाट अनुमोदित कालोनी का भाग न हो या प्लाट ऐसे क्षेत्र में न हो जिसके लिए जोनिंग विनियम XVII में उपबन्धित अनुसार छूट प्रदान की गई हो ; तथा
  - (ii) निदेशक की सन्तुष्टि के अनुसार प्लाट तक सड़क की व्यवस्था हो या सड़क बनी हुई हो।

# XII. विभिन्न प्रकार के भवनों के अधीन आच्छादित क्षेत्र, ऊँचाई और आकार.—

स्वतन्त्र से उपबन्धों के अनुसार होगी। अन्य वर्गों के मामले में विनियम XVI के अन्तर्गत लगाये जाने वाले वास्तुकला नियन्त्रण के अनुसार अधिकतम निर्मित क्षेत्र और फर्श क्षेत्र अनुपात निम्नानुसार होगा:—

क्रम संख्या	उपयोगिता की किस्म	भूमितल मन्जिल का अधिकतम निर्मित क्षेत्र	अधिकतम फर्श क्षेत्रफल अनुपात	भूमितल में दिये जाने वाले श्रेणी व प्रयोग
1	सरकारी कार्यालय	25 प्रतिशत	1.5	भूमितल में तीन स्तर तक पार्किंग एवं सुविधाएं दी जा सकती है, यदि वे जन स्वास्थ्य, अग्नि एवं निर्माण सुरक्षा की शर्तो को पूरा करता हैं।
2	वाणिज्यिक			
	क. एक्कीकृत कारपोरेट	40 प्रतिशत	1.5 — 1.75 ( जोनिंग प्लान अनुसार)	भूमितल में चार स्तर तक पार्किंग एवं सुविधाएं दी जा सकती है, यदि वे जन स्वास्थ्य, अग्नि एवं निर्माण सुरक्षा की शर्तो को पूरा करता है।
	ख. व्यक्तिगत एस.सी.ओ.	100 प्रतिशत	3.0	एकल भूमितल में स्टोर, लिफ्ट का मशीन रूम, रिर्कोड, गोदाम व स्ट्रांगरूम अधिकतम तीन मीटर तक दी जा सकती है, इसके अतिरिक्त अन्य कोई प्रयोग नहीं किया जा सकता।
	ग. बूथ	100 प्रतिशत	1.0	एकल भूमितल में अधिकतम तीन मीटर तक स्टोर रूम दिया जा सकता है।
3	भांडागार	60 प्रतिशत	0.75	भूमितल नहीं दिया जा सकता।

#### टिप्पण:-

भूमितल फर्श क्षेत्रफल अनुपात से अलग होगा।

भूमितल में भण्डारण प्रयोजन एन.बी.सी. कोड के अनुसार होगा।

# XIII वास्तुकला सम्बन्धी नियन्त्रण:-

प्रत्येक भवन पंजाब अनुसूचित सड़क तथा नियत्रित क्षेत्र अनियमित विकास निर्बन्धन नियम 1965 के नियम 50 के अधीन तैयार किए गए वास्तुकला सम्बन्धी नियन्त्रण के अनुसार होगा,

# XIV कृषि अचल में भूमि उपयोग में ढील :-

कृषि अचंल में पड़ी किसी भूमि के मामले में सरकार इस विकास योजना के उपबन्ध में निम्न लिखित हेतु ढील दे सकती है:--

- (क) भूमि के आवासीय अथवा औद्योगिक उपनिवेशन में उपयोग तथा विकास के लिए बशर्ते कि उपनिवेशक ने यह भूमि वास्तविक तिथि से पहले उक्त उपयोग तथा विकास के लिए खरीदी हो और उपनिवेशक नियमानुसार इस प्रयोजन के लिए अनुमति प्राप्त करता है।
- (ख) व्यक्तिगत स्थल के रूप में भूमि के उपयोग के लिए (औद्योगिक कालोनी से भिन्न) परन्तु यह कि:—
  - (i) वास्तविक तिथि से पूर्व भूमि खरीदी गई हो।
  - (ii) सरकार को संतुष्टि है कि उद्योग की आवश्यकता इस प्रकार की है कि उपयुक्त अंचल में वैकल्पिक आबंटन के नियतन की प्रतीक्षा नहीं की जा सकती;
  - (iii) भू-स्वामी यथा अपेक्षित नियमों के अधीन भवन निर्माण के लिए अनुमति प्राप्त करता है;
  - (iv) भू—स्वामी, निदेशक द्वारा निर्धारित अनुपातिक प्रभार जब भी कभी निदेशक द्वारा इस निमित्त मांग की जाये, उसके द्वारा अदा करने की प्रतिज्ञा करता है और अंतरिम अवधि में मल निकास की संतोषजनक व्यवस्था करता है।

व्याख्या :- विनियम में 'क्रय' (खरीद) शब्द का अर्थ पूर्व स्वामित्व अधिकारों को प्राप्त करना है तथा न कि पट्टाकर्ता हक, जैसे कि क्रय हेतु इकरारनामा इत्यादि।

- (ग) ऐसा स्थल रक्षा संकर्म अधिनियम, 1903 (1903 का 7) के तहत रक्षा संस्थापनाओं यदि कोई हो, के इर्द गिर्द अधिसूचित वर्जित पट्टी के अधीन न आता हो।
- XV. कृषि जोन में आबादी देह के बाहर फार्म हाउस की व्यवस्था:—ग्रामीण जोन में आबादी देह के बाहर फार्म हाउस की अनुमित केवल भूमि के उन वास्तविक स्वामियों को ही दी जायेगी जिनके पास शहर में कोई आवास नहीं है । कृषि क्षेत्र में फार्म हाउस की अनुमित का मुख्य उदेश्य उन कृषकों की आवासीय आवश्यकताओं को पूरा करना है जो बहुत छोटे कृषि भूमि के स्वामी हैं और अपने कृषि फार्म में रहते हुए अपनी आजीविका चला सकें । इस सन्दर्भ में आबादी देह के बाहर कृषि क्षेत्र में फार्म हाउस 2 एकड या इससे अधिक वाली भूमि पर निम्न प्रकार से अनुमत होगें:—

	फार्म हाउस का आकार	आवासीय इंकाई का मुख्य	मुख्य आवासीय इकाई
		भवन	का अनुशंगी भवन
(i) निर्मित	न्यूनतम २ एकड परन्तु विकास योजना मे	जैसा कि 250 वर्ग गज के	फार्म की भूमि का एक
क्षेत्र	प्रस्तावित सड़क आरक्षण/प्रस्तावित सड़क		प्रतिशत
	की चौड़ाई के अधीन आने वाला क्षेत्र भूमि	लिये लागू है।	(मजदूरों / नौकरों के
	उपयोग में परिवर्तन की अनुमति हेतु मान्य		क्वार्टरों के लिए 40
	नहीं होगा। किन्तु कृषि अंचल में पडने वाले		प्रतिशत से अधिक का
	आवेदित 2 एकड़ क्षेत्र मे से हरित पट्टी/		उपयोग नहीं किया
	प्रतिबधित पट्टी के अर्न्तगत आने वाले क्षेत्र		जायेगा)
	को छोड़ते हुए शेष क्षेत्र 1.5 एकड़ से कम		,
	नहीं होना चाहिए।		
	3 एकड़ तक	जैसा कि 375 वर्ग गज के	-सम-
		समकक्ष रिहायशी प्लाट के	
		लिये लागू है।	
	४ एकड़ तक तथा अधिक	जैसा कि 500 वर्ग गज के	-सम-
		समकक्ष रिहायशी प्लाट के	
		लिये लागू है।	
(ii) ऊंचाई त	तथा मंजिल	11 मीटर, तीन मंजिलें	4 मीटर, एक मंजिल

# (iii) दुरी

कृषि भूमि के किनारें से सब तरफ कम से कम 10 मीटर दूर बशर्ते कि यदि फार्म हाऊस से संबंद्ध भूमि सड़क के साथ लगती है तो गृह का निर्माण सड़क के किनारे से कम से कम निम्नलिखित दूरी पर किया जायेगा।

(क) जहां सड़क अनुसूचित सड़क का बाईपास या एक्सप्रैसवे है।

30 मीटर

100 मीटर

(ख) जहां सड़क अनुसूचित सड़क है या जैसा कि विकास योजना में दर्शाया गया हैं

10 मीटर

(ग) कोई अन्य सड़क

# (iv) पहुँच सड़क ≔

राजस्व रिकार्ड में वर्णित कोई राजस्व रास्ता / सड़क है।

# (v) निम्नतल:-

अधिकतम भूतल आच्छदन सीमा तक निम्नतल के लिए अनुमित दी जायेगी, किन्तु निम्नतल में शौचालय और स्नानगृह बनाने की अनुमित नहीं होगी।

# (vi) पुश्तवान, अटारी तथा परछती तल:-

पुश्तवान, अटारी और परछती तल की अनुमित भवन के भीतर उक्त प्रतिबन्धों और विकास योजना की अंचल विनियम भाग - II में दी गई परिभाषा में दिये गये, प्रतिबन्धों के अधीन दी जायेगी।

# (vii) सेवायें-जल आपूर्ति तथा जल निकास :-

(क) यदि फार्म गृह का निर्माण किया जाता है तो फार्म में मानव उपयोग के लिए अच्छी पीने योग्य जल आपूर्ति उपलब्ध होनी चाहिए ।

- (ख) डेरी फार्म के मामले में छायावान की सफाई हेतु खुली मल निकास नालियां अथवा ढकी हुई नालियों का प्रबन्ध किया जाये, सभी भवनों के मामले में वर्षा के पानी के निकास हेतु नालियों की व्यवस्था की जानी है।
- (ग) नियमों मे प्रावधान अनुसार मनुष्य और पशुओं के मल निस्तारण के लिए मलाश्य की व्यवस्था की जाये।
- (घ) मलाश्य और खुले कुएँ अथवा नलकूप के बीच दूरी नियमों में प्रावधान अनुसार होगी:
- (viii) स्वामी द्वारा फार्म हाऊस की मुख्य आवासीय इकाई एंव अनुषंगी भवन के इर्द–गिर्द चार दीवारी के निर्माण की अनुमित दी जायेगी तथा फार्म के शेष भाग के इर्द–गिर्द कंटीली तारों वाली बाड़ लगाने की अनुमित होगी ।
- (ix) कन्द्रीय भूजल मण्डल द्वारा अत्यधिक शोषित एवं सकंटमय घोषित क्षेत्र के अलावा बाकी के क्षेत्रों में फार्म हाऊस हेतु भूमि उपयोग में परिवर्तन की अनुमित मान्य होगी :

परन्तु सरकार कृषि अंचल के उचित उपयोग के लिए राज्य सरकार / राज्य अभिकरण द्वारा प्रयोजित किसी स्कीम के लिए फार्म के न्यूनतम आकार में संशोधन कर सकती है।

# XVII संचार टावरों की स्थापना :

नियंत्रित क्षेत्र के अन्दर संचार टावर स्थापित करने के लिए दिनांक 10 मार्च, 2015 की नीति जो समय–समय पर संशोधित की जा सकती है, के अनुसार स्वीकृति प्रदान की जायेगी ।

# XVIII भूकंम्पीय आपदा से सुरक्षा :

भारतीय मानक आई. एस. 1893 के भूकम्पीय क्षेत्र मानचित्र के अनुसार विकास योजना का क्षेत्र भूकम्पीय क्षेत्र के अंतर्गत आता है तथा अतः इसे उच्च आपदा क्षेत्र माना गया है । इसके मध्य नजर समग्र नवशहरी विकास घटना की सम्भावना "vii" की तीव्रता से आने वाले भूकम्प के विरुद्ध सुरक्षा की जांच की जाएगी तथा भवन तथा सवसंरचना में अपेक्षित भूकम्पीय मुकाबला करने के लिए उन्नत किया जाएगा ।

#### XIX विकास योजना में ढील:-

सरकार अत्यन्त कठिनाई की दशा में अथवा वास्तविक तिथि से पूर्व निर्मित किसी ढांचे को बचाने की दृष्टि से ऐसे विकास प्रभारों के भुगतान पर और ऐसी अन्य शर्तों पर वह लगाना उचित समझे, समान तथा न्याय के सिद्धान्त पर विकास योजना के किसी भी उपबन्धों में ढील दे सकती है।

परिशिष्ट क भूमि उपयोग का वर्गीकरण

मुख्य कोड	उपकोड	मुख्य वर्ग	<b>उपवर्ग</b>
400		परिवहन तथा संग	वार
	420		सड़कें, सड़क परिवहन डिपो और पार्किंग क्षेत्र
500		जन उपयोगितायें	
	510		जल आपूर्ति संस्थापन जिसमें शोधन संयंत्र भी शामिल हैं
	520		जल निकास और सफाई संस्थापन जिनमें निस्तरण कार्य भी शामिल हैं
	530		बिजली संयंत्र उपस्टेशन आदि
	550		ठोस कूड़ा प्रबन्धन
700		खुले स्थान	
	720	· ·	स्टेडियम, क्रीडा मैदान
	730		अन्य मनोरंजनात्मक संबंधी उपयोग
	750		पैट्रोल पम्प स्टेशन तथा बस पंक्ति शैल्टर
800		कृषि भूमि	
	840		चराई भूमि तथा चरागाहें
	850		संरक्षित वन के लिए आरक्षित
900		विशेष अंचल	मनोरंजन, सरकारी कार्यालय, वाणिज्यिक, सामुहिक आवास एवं सांस्थिक
			उपयोग विशेष अंचल में शामिल होंगे।
1000		प्रतिबंधित अंचल	सुन्दरता और पर्यावरण विकास कार्य, मन्दिर, संग्रहालय, विश्राम गृह एवं
			पुलिस पोस्ट

II

# परिशिष्ट ख

# I

वाणिज्यिक	र्यासाय ख	
(i)	अ <b>यल</b>   परचून व्यापार	
(ii)	्र थोक व्यापार	
(iii)	भांडागार और भंडारण	
(iv)	वाणिज्यिक कार्यालय और बैंक	
(v)	रैस्तरा तथा परिगमन आवास गृह जिसमें धर्मशाला और पर्यटक गृह आदि रिहायशी स्थान प्रदान करने वाले सार्वजनिक सहायता संस्थान जैसे शामिल है।	जैसा कि मुख्य उपयोग की स्थानीय जरूरतों और सैक्टर योजना में
(vi)	सिनेमा, होटल, मोटल तथा अन्य स्थान तथा वाणिज्यिक आधार पर चलने वाले और लोगों के इकट्ठा होने वाले स्थान जैसे थियेटर, क्लब, ड्रामा क्लब आदि	उनके लिए निर्धारित स्थलों पर या कालोनियों की अनुमोदित अभिविन्यास
(vii)	व्यावसायिक संस्थापनायें	योजनाओं में अपेक्षित है
(viii)	प्रथम तथा उच्चतर मंजिलों पर निवास	तथा सरकार द्वारा निश्चित नीति / मापदंडों
(ix)	स्थानीय सेवा उद्योग	के अनुसार।
(x)	जन उपयोगिता भवन	
(xi)	पैट्रोल, फीलिंग स्टेशन और सर्विस गैरेज	
(xii)	माल चढ़ाने और उतारने वाले यार्ड	
(xiii)	वाहन खड़े करने के स्थान, बस स्टाप, टैक्सी, टांगा और रिक्शा स्टैंड	
(xiv)	नगर पार्क	
(xv	संचार टावर	
(xvi)	कोई अन्य उपयोग, जिसके लिए सरकार लोकहित में निर्णय लें।	
परिवहन त	 था संचार अंचल	
(i)	रेलवे यार्ड रेलवे स्टेशन और साईडिंग	सैक्टर योजना में
(ii)	परिवहन नगर, सड़के और परिवहन, डिपों और पार्क क्षेत्र	निर्धारित स्थलों पर ।
(iii)	हवाई अड्डा और हवाई स्टेशन	
(iv)	तार घर और टेलीफोन कार्यालय	
(v)	प्रसारण केन्द्र	
(vi)	दूरदर्शन केन्द्र	
(vii)	अनुमोदित स्थलों और स्थानों पर कृषि, बागवानी और नर्सरियां	
(viii)	पैट्रोल पम्प और सर्विस गैरेज	
(ix)	पार्किंग स्थल, बस स्टाप / शैल्टर, टैक्सी, टांगा और रिक्शा स्टैंड	
(x)	संचार टावर	
(xi)	वेयर हाऊस (सैक्टर के कुल क्षेत्रफल का अधिकतम 5 प्रतिशत)	

III	जन उपयोगिता									
	(i)	 जल वितरण, स्थापन	ना इसमें शोध	न संयंत्र भी १	गमिल है।		सेक्टर	यो	जना में	
	(ii)	जल निकास और स	म्फाई स्थापना	एं इसमें निपट	प्रन कार्य भी इ	शामिल है।				
	(iii)	इलैक्ट्रिक पावर प्ला		स्टेशन में ग्रिड	सब स्टेशन	भी शामिल है।				
	(iv)	गैस स्थापना तथा गै								
	(v)	ठोस अपशिष्ठ निपट								
IV	सार्वजनिक (i)	तथा अर्धसार्वजनिक ।								
	(ii)	सरकारी कार्यालय,			•	पुलिस थाना				
	(iii)	शैक्षणिक, सांस्कृतिक		संस्थायें इत्य	ादि					
	(iv)	चिकित्सा स्वास्थ्य स					सेक्टर	ग्रो	जना में	
	(1V)	नागरिक, सांस्कृतिक हाउस इत्यादि जो वि					निर्धारि			
	(v)	रक्षा स्वामित्व वाली	S	( 411 11 2 4 4)	14/(1 4/ 61)					
	(vi)	ढाबा, रेस्टोरेन्ट निम्न								
				_	*	वाणिज्यिक	orfo-		a	
	क्रम संख्या	सुविधा का नाम	क्षे न्यूनतम	त्र अधिकतम	सैक्टर में कुल	वााणाज्यक घटक	अधिव भूत		तल क्षेत्र अनुपात	
	4		υ,		सुविधाएं	50 वर्गमीटर	प्रयोग		0.50	
	1	ढाबा	500 वर्गमीटर	1000 वर्गमीटर	2	५० प्रामाटर	50 प्रतिशत 0.		0.50	
	2	रैस्टोरैन्ट	1000 वर्गमीटर	2000 वर्गमीटर	2	10 प्रतिशत	30 प्रति	तेशत	1.50	
	(vii)	संचार टावर								
	(viii)	कोई अन्य उपयोग	जिसके संबंध	में सरकार द्वा	रा जनहित में	निर्णय लिया ग	या हो।			
V	खुले स्थान	T								
	(i)	खेलकूद मैदान, स	टेडियम तथा	खेल मैदान						
	(ii)	पार्क तथा हरित प	गट्टी					तथा	शक नगर ग्राम	
	(iii)	कब्रिस्तान, श्मशान	। घाट इत्यावि	[				विभा	जिना ग गणा द्वारा	
	(iv)	निदेशक की अनुम् शैल्टर	निदेशक की अनुमति से सड़कों के साथ मोटर पयूल फीलिंग स्टेशन, बस पंक्ति शैल्टर							
	(v)	उपयोगिता सेवाअ	अनुसूचित सड़कों एवं मुख्य सड़कों के साथ हरित पट्टी में सार्वजनिक उपयोगिता सेवाओं जैसा कि प्रेषण लाईने, संचार लाईनें, जल आपूर्तिं, सीवरेज लाईने, ड्रेनेज लाईन							
	(vi)	जल निकाय, झील	न और जल पु	र्नभरण						
	(vii)	संचार टावर								
	(viii)	सरकार की अनुम	ति से कोई अ	न्य मनोरंजन	संबंधी उपयोग	ΤΙ				

X 7 T	बिल्कुल निर्णि	षेद्ध उपयोग	
VI		उचित लाईसेंस के बिना पैट्रोलियम और अन्य प्रज्वलनीय सामग्री का भंडारण	
VII	कृषि अंचल		
	(i)	कृषि, बागवानी, डेरी और मुर्गी पालन	
	(ii)	आबादी देह में गांव घर	
	(iii)	अंचल विनियम XIX में निर्धारित प्रतिबन्धों के अध्ययीन आबादी देह के बाहर फार्म हाऊस	निदेशक नगर तथा ग्राम आयोजना
	(iv)	वन रोपण विकास तथा आमोद—प्रमोद के लिए उसका कोई भाग	विभाग
	(v)	आबादी देह के समीप वर्तमान गांव का विस्तार यदि यह परियोजना, केन्द्र सरकार या राज्य द्वारा अनुमोदित परियोजना हो ।	हरियाणा द्वारा अनुमोदित स्थलों पर
	(vi)	दुग्ध अवशीतन केन्द्र और पैसच्यूरीकरण केन्द्र	तथा सरकार
	(vii)	बस अङ्डा और रेलवे स्टेशन	द्वारा निश्चित नीति /
	(viii)	अनिवार्य भवनों सहित हवाई अङ्डा	नात / मानदंडों के
	(ix)	बेतार केन्द्र	अनुसार।
	(x)	निदेशक द्वारा अनुमोदित स्थलों पर अनाज गोदाम, भंडारण स्थल	
	(xi)	मौसम कार्यालय	
	(xii)	भू—जल निकास और सिचाई, वन बिजली केन्द्र और सिचाई के लिए नलकूप	
	(xiii)	टेलीफोन और बिजली प्रेषण लाईनें और खम्भे	
	(xiv)	नियम के अधीन रहते हुये तथा अनुमोदित सीलों पर खनन तथा उत्खनन कार्य जिसमें चूना तथा ईंटों के भट्टे पत्थर खादाने और क्रेशिंग शामिल है।	
	(xv)	श्मशान और कब्रिस्तान	
	(xvi)	पेट्रौल पम्प ओर सर्विस गैरेज	
	(xvii)	पन बिजली / थर्मल बिजली संयंत्र थर्मल उपकेद्र	
	(xviii)	निदेशक के अनुमोदन से लिक्वीड पैट्रोलियम गैस भण्डारण गोदाम	

(xix)

- (क) रक्षा प्रतिष्ठान के इर्द—गिर्द प्रतिबन्धित पट्टी के बाहर ग्रामीण उद्योग योजना/छोटे पैमाने की आद्यौगिक ईकाईयों के रूप में पंजीकृत प्रदूषण रहित उद्योग जैसा ऐसे प्रतिष्ठान के लिए लागू है, यदि कोई हो बशर्ते कि वे निम्नलिखित में से किसी एक शर्त को पूरा करें।
- (i) वर्तमान गांव आबादी देह के क्षेत्र के भीतर के आसपास की पट्टी के आधे किलोमीटर में स्थित हो और अनुसूचित सड़क, राष्ट्रीय राजमार्ग और राज्य राजमार्ग से भिन्न किसी सार्वजनिक सड़क / रास्ते द्वारा उस तक पहुंचा जा सकता हो; या
- (ii) सार्वजिनक सड़क / रास्ते पर जो कम से कम 30 फुट चौड़े हो, अनुसूचित सड़कों, राष्ट्रीय राजमार्ग तथा राज्य राजमार्ग से भिन्न उक्त पद है (i) में उल्लेखित आधा किलोमीटर की अंचल से बाहर पहुंच सड़क के साथ-साथ 100 मीटर के अन्दर की ओर
- (ख) मध्यम एवं बड़े आकार के प्रदूषण रहित कृषि आधारित उद्योग अनुसूचित सड़क,

राष्ट्रीय राजमार्ग तथा राज्य अनुसूचित राजमार्ग से भिन्न सार्वजनिक सड़क / रस्ते पर जो कम से कम 30 फुट चौड़े हों।

ऐसा स्थल रक्षा संकर्म अधिनियम, 1903 के तहत रक्षा सस्थापनाओं यदि को हो, के इर्द गिर्द घोषित वर्जित पट्टी के अन्तर्गत न आता हो।

राष्ट्रीय राजमार्ग / अनुसूचित सड़क पर प्रतिबन्धित क्षेत्र / हरित पट्टी से बाहर ढाबा, रैस्टोरैन्ट, मोटल, रिजोर्ट तथा मनोरंजन पार्क / खेलकूद पार्क निम्न प्रकार से है:—

अधिकत अनुज्ञेय क्षेत्र वाणिज्य फर्श क्रम क्रिया संख्या क्षेत्र क म अधिकतम न्यूनतम क्लाप अनुपात घटक भूतल क्षेत्र ढाबा 1000 1 एकड 50 वर्ग 1. 40 % 0.40% वर्ग मीटर मीटर रैस्टोरैन्ट 2000 2 1 एकड 15 30 % 1.50% प्रतिशत वर्ग मीटर मोटल 2.5 5 एकड 3 15 30 % 1.50% बारात घर प्रतिशत एकड की स्विधा सहित रिर्जीट 10 एकड 15 30 % 1.50% एकड प्रतिशत मनोरंजन 10 एकड 5 2.5 15 30 % 0.50% पार्क / थी प्रतिशत एकड म पार्क

निदेशक नगर तथा ग्राम आयोजना विभाग हरियाणा द्वारा अनुमोदित स्थलों पर तथा सरकार द्वारा निश्चित नीति/ मानदंडों के अनुसार।

(xx)

परन्तु यदि स्थल राष्ट्रीय राजमार्ग पर स्थित है तो पहुंच अनुमित भारतीय राष्ट्रीय राजमार्ग प्राधिकरण से प्राप्त करनी है तथा यदि स्थल अनुसूचित सड़क पर स्थित है तो पहुंच अनुमित कार्यकारी अभियन्ता, लोक निर्माण विभाग (भवन तथा सड़के) से प्राप्त करनी होंगी।

सर्विस गेराज और बिक्री / प्रदर्शन स्थल-कम-सर्विस गैराज

MAN				11 (90)				
क्रम	सुविधा	क्षेत्र प		वाणिज्य	अधिक	फर्ष	पहुँच	ऊँचा
संख्या	का नाम	+	İ	क	तम	क्षेत्र	सड़क	ई
				प्रयोग	भूतल	अनु		
					प्रयोग	पात		
		न्यून	तम					
		अधिव						
1	सर्विस	1/	1	शून्य	60%	1.	न्यूनतम	18
	गैराज	2				25	18 मीटर	मीटर
							या	
							सैक्टर	
							सड़क के	
							साथ	
							सर्विस	
							रोड़	
2	बिक्री /	1/	2	अनुज्ञेय	60 %	1.	न्यूनतम	18
	प्रदर्शन	2		फर्श		25	18 मीटर	मीटर
	स्थल-			क्षेत्र			या	
	कम—			अनुपात			सैक्टर	
	सर्विस			का			सड़क के	
	गैराज			10%			साथ	
							सर्विस	
							रोड़	
		•	•					

निदेशक नगर तथा ग्राम आयोजना विभाग हरियाणा द्वारा अनुमोदित स्थलों पर तथा सरकार द्वारा निश्चित नीति/ मानदंडों के अनुसार।

- वाणिज्यिक घटक पर फीस और शुल्क वाणिज्यिक दरों पर लगाया जाएगा ।
- ऊपर दिए मानदंडों को पूरा करने उपरान्त मौजूदा / पहले से ही सी0 एल0 यू0 प्राप्त सर्विस गेराज को बिकी / प्रदर्शन स्थल को अनुमित के लिए विचार किया जाएगा।

# बैंक्विट हालः

(xxi)

अनुज्ञेय अचंल	कृषि अचंल
पहुंच	1. पहुंच सड़क की चौड़ाई कम से कम 18 मीटर होनी चाहिए।
	<ol> <li>यदि स्थल अनुसूचित सड़क पर स्थित हो तो इस रास्ते की अनुमित कार्यकारी अभियंता, लोक निर्माण विभाग (भवन तथा सड़कें) से अपेक्षित है।</li> </ol>
	3. राष्ट्रीय राजमार्ग से भी पहुंच विचारी जा सकती है, यदि स्थल चौराहा / पहुंच मार्ग से न्यूनतम दूरी मानक पूरा करते हो तथा न्यूनतम ७ मीटर चौडी सेवा सड़क पर अवस्थित हो या आवेदक भारतीय राष्ट्रीय राजमार्ग प्राधिकरण से पहुंच की पूर्व अनुज्ञा प्रस्तुत करता है।
अपेक्षित क्षेत्र	न्यूनतम २.५ एकड़
	अधिकतम 5.00 एकड़

1			1
	फर्श क्षेत्र	0.50	
	अनुपात भूतल क्षेत्र	30 प्रतिशत	
	मूतल बात्र	30 श्रातशत	
	परिवर्तन प्राभार	वाणिज्यिक उपयोग के लिए विदित दर का 50 प्रतिशत	
	फर्श क्षेत्र	उपहार दूकान, एस टी डी बूथ, खिलौना केन्द्र, तथा फूलों	
	अनुपात के	की दूकाने इत्यादि के लिए अनुज्ञात फर्श क्षेत्र अनुपात का	
	भीतर अनुज्ञेय	10 प्रतिशत	
	अनुशांगिक		
	उपयोग		
	पार्किंग	स्थल क्षेत्र का न्यूनतम 25 प्रतिशत	
(xxii)	माईक्रोवेव स्तूप/र	टेशन, भूकम्प केन्द्र तथा दूरसंचार केन्द्र	
(xxiii)	संचार टावर		
(xxiv)		बंधित तैयार मिश्रण, कंकीट संयंत्र, वेट मिश्रण सयंत्र, गरम	
		के लिए सरकार या सरकारी अभिकरण द्वारा संविदा या कार्य	
	दिया गया है तथा	निबन्धन आधार पर स्थापित किया जाता है।	
(xxv)	कोई अन्य उपयोग	जिसके लिए सरकार लोकहित में निर्णय ले सकती है।	

पी. राघवेन्द्र राव, अतिरिक्त मुख्य सचिव, हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग।

#### HARYANA GOVERNMENT

#### TOWN AND COUNTRY PLANNING DEPARTMENT

# Notification

The 24th August, 2015

**No. CCP(NCR)/DDP (Ad-Badri)/2015/2461.** In exercise of the powers conferred by Sub-section (4) of Section 5 of the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963), the Governor of Haryana hereby publishes the Draft Development Plan-2031AD for the controlled area around Tirth Ad-badri, district Yamuna Nagar, declared *vide* Haryana Government Town and Country Planning Department, notification No. CCP(NCR)/2003/YN-IV/1791, dated the 18th August, 2003 alongwith restrictions and conditions as given in Annexures 'A' and 'B' proposed to be made applicable to the controlled areas covered by it specified in Annexure 'B'.

Notice is hereby given that the draft development plan shall be taken into consideration by the Government on or after the expiry of a period of thirty days from the date of publication of this notification in the Official Gazette together with objections and suggestions, if any, which may be received by the Director, Town and Country Planning Department, Haryana, S.C.O. 71-75 (First to Third Floor), Sector-17 C, Chandigarh, from any person in writing in respect of this draft development plan before the expiry of the period so specified.

#### **DRAWINGS**

- 1. Existing Land use Plan Drawing No. DTP(Y)/150/03 dated the 15th April, 2003.
- 2. Draft Development Plan of Ad-badri-2031AD Drawing No. DTP(Y)/316/2014 dated the 05th July 2014.

#### ANNEXURE-A

# EXPLANATORY NOTE ON THE DRAFT DEVELOPMENT PLAN-2031AD FOR THE CONTROLLED AREA AROUND TIRTH AD-BADRI, DISTRICT YAMUNANAGAR.

#### 1. INTRODUCTION

Ad-Badri is an ancient Hindu's Pilgrimage. A pristine temple of Lord Vishnu (Badri Narain) and goddess Laxmi is located on a hill at a height of about 455 metres from mean sea level. The origin of holy river Saraswati of Vedic era (now disappeared) is also located near the shrine. Archaeological Survey of India has discovered the remains of some ancient civilization at Ad-Badri and its surrounding areas. Statues of Lord Shiva, Lord Ganesha and Goddess Parvati belonging to 9th and 10th centuries and Mahatma Budha of 11th and 12th centuries have also been discovered near the shrine. The place is gaining importance because of religious sentiments and tourism potential. Lacs of devotees visit it during Kapal Mochan fair.

# 2. LOCATION, REGIONAL SETTING AND CLIMATE

Tirth Ad-Badri is located at a distance of about 42 Kilometres from Yamuna Nagar and about 18 Kilometres from Bilaspur towards its north. A village link road (Ranjeet Pur- Kathgarh road) connects the place with Bilaspur-Dhanora Road. The shrine is situated on a low hill of shivalik at a height of about 455 metres from mean sea level adjoining State boundary of Himachal Pardesh. The average annual rainfall is about 1250 mm. The average sub surface water level is about 50 feet deep having PH value ranging from 7.5 to 8, which is considered good for crops as well as drinking purposes. The composition of soil is sandy loam (with clay particles), which is considered good for crops.

#### 3. NEEDS FOR DECLARATION OF CONTROLLED AREA

Ad Badri tirth is, not only, an ancient pilgrimage but also a very important archaeological site. It is believed to be the origin of holy ancient river Saraswati which has now disappeared. The Central Government has granted funds for carrying out excavation by Archaeological Survey of India and construction of a museum. The remains of ancient civilization have also been discovered at Ad Badri and its surrounding areas. Number of pilgrims is increasing every year. Under the scenario it was essential to prevent haphazard growth and ensure planned development of this holy place. Keeping in mind, a controlled area was declared around the shrine *vide* Haryana Government Town and Country Planning Department Notification No. CCP(NCR)/2003/YN-VI/1791, dated the 18th August, 2003, published in Haryana Government Gazette dated the 26th August, 2003.

#### 4. LAND USE PROPOSALS

The controlled area has been declared mainly to keep legacy and sanctity of this holy place intact. In view of this, no population projection has been made. Consequently, no urbanization proposal has been made in the Draft Development Plan. The entire controlled area has been divided into different zones with designated land uses. The distribution of various land uses is shown below in the table.

#### Serial %age of total area Land use Area in hactares Number Transport & Communication 13.64 6.88 2. Public Utilities 10.57 5.33 3. Open Spaces 63.13 31.84 4. Special Zone 20.53 10.35 Restricted Zone 90.41 40.60 5. Total 198.48 100.00

#### **Distribution of Land Uses**

# A brief description of land uses follows:

#### (i) Transport and Communication

Owing to non-existence of urbanization proposal, the volume of vehicular or pedestrian traffic is not expected to be very heavy, except during the 'Kapal Mochan Mela'. Hence no major system of road had been proposed. However, existing road system needs to be strengthened in view of the increasing importance of the place. The following proposals are made in this regard.

- A site measuring 5 acres earmarked for bus stand in special zone.
- Widening of existing Ranjeetpur-Kathgarh-Ad Badri Road to 30 metres in the plain and 15 metres in hilly terrain.

- Two bridges are proposed for connecting the archaeological sites situated on the eastern bank of Somb River
- 15 m wide pathway is proposed along the eastern bank of river Somb for pedestrians.
- Two pathways have been created by the General Public. The first is between Ad-Badri to Mata Mantra Devi Temple and another starts from proposed 5 metres wide pathway upto Mata Mantra Devi Temple. However, both these pathways are not shown in revenue record. The width of these pathways whereas from 5 feet to 10 feet which has been proposed to be widened to 5 metres.

The total land allocated under this use is about 13.64 hactares.

#### (ii) Public Utilities

An area of 10.57 hactares has been earmarked to accommodate Public Utilities e.g. water works, Electric Sub-Station, Solid waste disposal, sanitary and drainage installation sites. A site measuring 5 hactares has been earmarked for sewerage treatment plant inside controlled area near the bank of Somb River.

# (iii) Open Space

In order to maintain clean, serene and salubrious environment of the place, development of a park and for other recreational uses an area of 63.13 hactares of land has been allocated under this use.

# (iv) Special Zone

Keeping in view the religious character of the place the provision of special zone has been made comprising an area of 20.53 hactares of land. It shall include institution, office, recreational buildings and area with residential, commercial and other uses ancillary to the above-mentioned main uses.

#### (v) Restricted Zone

An area measuring 90.41 hactare of land spreader on either sides of Somb River surrounding the archaeological, sites has been proposed as restricted zone. The boundary of restricted zone has been earmarked as per the notification of the Forest Department. No construction activity shall be allowed with in this zone, except erection or re-erection of temple, museum, rest house, police post and other development works needed for beautification and environmental improvement of the area.

# (vi) Protected Forest Zone

An area about 2/3rd of the total land area is reserved as protected Forest Zone. No construction activity shall be allowed with in this zone, except other development works needed for beautification and environmental improvement of the area.

# (vii) Agriculture Zone

Apart from the land proposed under various uses, the remaining controlled area is proposed to be reserved as Agriculture Zone. However, it would not eliminate essential building development within this area, such as extension of the existing village contiguous to abadi-deh, if undertaken as a project approved or sponsored by the Government and other ancillary facilities necessary for the maintenance and improvement of agricultural land.

#### 5. Zoning Regulations

The legal sanctity to the proposal regarding land use is being given effect by a set of zoning regulations, which form part of this development plan. These regulations will govern the change of the land use and standards of development. They also very elaborately detailed out allied and ancillary uses which will be permitted in the various major land uses and stipulate that all the change of land use and development shall be in accordance with the detail shown in the sector plan thereby ensuring the preparation of detailed sector plan for each sector to guide development and enforce proper control.

#### ANNEXURE B

#### **Zoning Regulation**

Governing use and Development of Land in the controlled area around Ad Badri as shown in Drawing No. DTP(Y)/316/2014 dated the 05th July, 2014.

#### I. General:

- (1) These Zoning Regulations, forming part of the development plan for the controlled area around Ad Badri shall be called Zoning Regulations of the Draft Development Plan for Controlled Area around Ad Badri.
- (2) The requirements of these regulations shall extend to the whole of the area covered by the Draft development plan and shall be in addition to the requirements of the Punjab Scheduled Roads and

Controlled Areas Restriction of Unregulated Development Act, 1963 (Punjab Act No. 41 of 1963), and the rules framed there under:

#### **II. Definitions:**

#### In these regulations:

- (a) 'Approved' means approved under the rules;
- (b) 'Building rules' means the rules contained in Part-VII of the rules;
- (c) 'Drawing' means Drawing No. DTP(Y)/316/2014 dated the 05th July, 2014.
- (d) 'Floor Area Ratio' (FAR) means the ratio between the total floor area of a building on all floors and the total area of the site:
- (e) "Farm House" shall means a house constructed by the owner of a Farm at his land for the purpose of:-
  - (i) Dwelling unit i.e. main use
  - (ii) Farm shed i.e. Ancillary use.

#### Notes:-

- I. The construction of the farm house shall be governed by the restrictions given under clause XIX regarding "Provision of Farm House outside abadi-deh in Agricultural Zone";
- **II.** The farm sheds regarding building control and site specifications shall be governed by the restrictions mentioned in clause XIX;
- (f) "Green Belt" shall mean, strips of land along sector/arterial road shown in the Development Plan, primarily meant for the widening of the sector/arterial road in future or for laying essential services;
- (g) "Loft" means an intermediary floor on a residual space in a pitched roof; above normal floor level with a maximum height of 1.5 metres and which is constructed or adopted for storage purposes;
- (h) 'Material Date' means the date of publication of notification of various controlled areas declared as under:

Serial Number	Name of the controlled area and notification No.	Material date
1.	Controlled area around Ad Badri Tirth, <i>vide</i> Haryana Government Gazette notification no. CCP(NCR)2003/YN-VI/1791, dated August 18, 2003	August 26, 2003

- (i) "Mezzanine Floor" means and intermediate floor above ground level with area of mezzanine restricted to 1/3<sup>rd</sup> of the area of that floor and with a minimum height of 2.2 metres;
- (j) "Non-conforming use" in respect of any land or building in a controlled area means the existing use of such land or building which is contrary to the major land use specified for that part of the area in the Development Plan.
- (k) "Public Utility Service Building" means any building required for running of public utility services such as water-supply, drainage, electricity, post and telegraph and transport and for any municipal services including a fire station.
- (l) "Rules" means the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Rules, 1965;
- (m) "Site Coverage" means ratio expressed in percentage between the area covered by the ground floor of building and the area of the site;
- (n) "Subservient to Agriculture" means development and activities, which are required to assist in carrying out the process of agriculture such as tubewells, pump chambers, wind mills, irrigation drain, pucca platforms, fencing and boundary walls not more than 4 ft. high and with maximum 3ft. high fencing, water hydrant etc.;
- (o) The terms "Act", "Colony", "Coloniser", "Development Plan", "Sector" and "Sector Plan" shall have the same meaning as assigned to them in the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963) and Rules, 1965; and
- (p) any other term shall have the same meaning as assigned to it in the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963).

# III Major Land Uses/Zones:

- (i) Transport and Communication
- (ii) Public Utilities
- (iii) Open Spaces.
- (iv) Special Zone
- (v) Restricted Zone
  - Classification of major land uses is according to Appendix 'A'.

- **IV Division into sectors:** Major land uses mentioned at serial Nos. (i) to (v) in zoning regulation-III above, which are land uses for building purposes, have been divided into sectors as shown on the drawing, each sector shall be designated by the number as indicated on the drawing.
- **V Detailed land uses within major uses:** Main, ancillary and allied uses, which are subject to the other requirements of these regulations and of the rules, may be permitted in the respective major land uses zones are listed in Appendix B sub-joined to these Zoning Regulations.
- VI Sectors not ripe for development: Notwithstanding the reservation of various sectors for respective land uses for building purposes, the Director may not permit any changes in their land use or allow construction of building thereon from consideration of compact and economical development of the controlled area till such time as availability of water supply, drainage arrangement and other facilities for these sectors are ensured to his satisfaction.

# VII Land reservations for major roads:

(1) Land reservation for major roads marked in the Drawing shall be as under:

Serial	Classfication	Road	Land Reserved
Number			
1	V-1(a)	Existing Ranjeetpur	To be widened to 30 metres from point "A" to
		Kathgarh-Ad Badri Road	"A1" and 15 metres from point "A1" to point
			"A2" with 30 metres green belt on either
			sides.
2	V-1(b)	Existing Kathgarh to Rampur	To be widened upto 30 metres
		Gainda	

(2) Width and alignment of other roads shall be as per sector plans or as per approved layout plans of colonies.

#### VIII Non-conforming uses either existing or having valid change of land use permission

- (1) With regard to the existing projects located in the zones other than conforming-use zone in the Development Plan, such non-conforming uses shall be allowed to continue for a fixed period to be determined by the Director, but not exceeding ten years; provided that the owner of the building concerned:-
  - (a) undertakes to pay to the Director, as determined by him the proportionate charges towards the external development of the site as and when called upon by the Director to do so in this behalf;
  - (b) during the interim period makes satisfactory arrangements for the discharge of effluent to the satisfaction of the Director; and
  - (c) shall not be allowed to expand the existing project within the area of non conforming use.
- With regard to the projects having valid change of land use permissions, and located in the zones other than conforming-use zone in the Development Plan, such non-conforming uses shall be allowed to continue, provided that the owner of the building concerned:-
  - (a) undertakes to pay to the Director, as determined by him the proportionate charges towards the external development of the site as and when called upon by the Director to do so in this behalf; and,
  - (b) during the interim period makes satisfactory arrangements for the discharge of effluent to the satisfaction of the Director.

#### IX Discontinuance of non conforming uses:

- (1) If a non-conforming use of land has remained discontinued continuously for a period of two years or more, it shall be deemed to have been terminated and the land shall be allowed to be re-used or redeveloped only according to the conforming use.
- (2) If a non-conforming use building is damaged to the extent of 50 percent or more of its reproduction value by fire, flood, explosion, earthquake, war, roit or any other natural calamity, it shall be allowed to be re-developed only for a conforming use.
- (3) After the discontinuance of projects included under clause IX, the land shall be allowed to be redeveloped or used only for conforming use.
- (4) After a lapse of period fixed under clause IX (1), the land shall be allowed to be redeveloped or used only for conforming use.
- X The development to conform to sector plan and zoning plan: Except as provided in regulation IX, no land within major land use shall be allowed to be used and developed for building purposes unless the proposed use and development is according to the details indicated in the sector plan and zoning plan or the approved colony plan in which the land is situated.

- XI Individual site to form part of approved layout or zoning plan: No permission for erection or re-erection of building on a plot shall be given unless-
  - (i) the plot forms a part of an approved colony or the plot is in such area for which relaxation has been granted as provided in regulation XVII; and
  - (ii) the plot is accessible through a road laid out and constructed upto the situation of the plot to the satisfaction of the Director.
- XII Site coverage, height and bulk of building under various types of buildings:- In the case of other categories, the maximum coverage and the floor area ratio, subject to architectural control, as may be imposed under regulation XVI shall be as under:

Sr.	Type of use	Maximum	Maximum	Tier and Uses to be permitted in the Basement.
No.		Ground Floor	Floor Area	-
		Coverage	Ratio	
1	Government	25%	1.5	3 Level basement with the provision of parking and
	offices			services may be allowed if it satisfies the public health,
				fire and structural safety requirements.
2	Commercial:			
	(a) Integrated	40%	1.5 - 1.75	4 Level basement with the provision of parking and
	Corporate	4070	(As per	services may be allowed if it satisfies the public health,
	Corporate		zoning plan)	fire and structural safety requirements.
	(b) Individual	100	3.0	Single basement not exceeding 3 mtrs. shall be permitted
	SCO's			for storage, machine room of lifts, record, godowns and
				strong rooms and only ancillary to the permissible use of
				the site and for no other purposes.
	(c) Booths	100	1.0	Single basement not exceeding 3 mtrs. shall be permitted
				for storage.
3	Warehousing	60%	0.75	No basement shall be permitted.

#### Note:

- Basement floor shall be permitted free of FAR.
- Storage material in the basement shall be in accordance with the provisions of National Building Code.
- XIII Building lines in front and rear of buildings: These shall be provided in accordance with rules 51, 52 and 53 of the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Rules, 1965
- **XIV Architectural control:** Every building shall conform to architectural control prepared under rule 50 of the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Rules, 1965.
- **XV** Relaxation of agricultural zone: In the case of any land lying in Agriculture zone, Government may relax the provisions of this development plan:-
  - (a) For use and development of the land into a residential or industrial colony provided the colonizer has purchased the land for the said use and developed prior to the material date and the colonizer secures permission for this purpose as per Rules.
  - (b) for use of land as an individual site (as distinct from an industrial colony)

# Provided that-

- (i) the land was purchased prior to the material date;
- (ii) the Government is satisfied that the need of the industry is such that it cannot await alternative allotment in the proper zone;
- (iii) the owner of the land secures permission for building as required under the Rules;
- (iv) the owner of the land undertakes to pay to the Director, as determined by him, the proportionate charges as and when called upon by the Director in this behalf and during the interim period makes satisfactory arrangement for discharge of effluent.

#### **Explanation**

- The word 'purchase' in the regulation shall mean acquisition of full proprietary rights and no lesser title, such as agreement to purchase etc.
- (c) The site should not fall within restricted belt notified under the 'Works of Defence Act, 1903' around Defence installations, if any.
- XVI Provision of farm house outside abadi-deh in Agriculture Zone: Farmhouses shall be allowed only for bonafide use of landowner(s) provided he does not own a house in any urban area because the real object for allowing farmhouses in agriculture zone is to meet the housing needs of the farmers on a small portion of the farm so that he can take care of his agriculture produce while living on that farm. Hence, a farm

house in agriculture zone, outside abadi-deh may be allowed if the area of the land is 2 acres or more on the following conditions:-

	Size of farm house	Main building of the dwelling unit	Ancillary building of main dwelling unit
(i) Site Coverage	2 acres minimum but CLU permission for the area falling under road reservation/proposed road widening as per Development Plan, shall not be considered. However the net area should not be less than 1.5 acres after excluding the area falling under the green belt/restricted belt and falling in Agriculture zone from applied area of 2 acres.	As applicable to residential plot equivalent to 250 square yards.	l percent of the farm land (not more than 40% shall be used for labour/servant quarters)
	Upto 3 acres	As applicable to residential plot equivalent to 375 square yards.	-do-
	Upto 4 acres and above.	As applicable to residential plot equivalent to 500 square yards.	-do-
(ii) Height and	Storey	11 metres, three storeyed.	4 metres, single Storey.

(iii) Set back: It shall be at least 10 metres away from the edge of the agriculture land on all sides provided that if land attached to the farm house abuts a road, the house shall be constructed with a minimum set back from the edge of the road as under:-

(a) Where the road is bye-pass to a scheduled road or an : 100 metres

expressway.

(b) Where the road is a scheduled road or as shown in the : 30 metres

Development Plan

(c) Any other road : 10metres

(iv) Approach road Any revenue rasta/road defined in the revenue record.

(v) Basement Basement shall be permitted to the maximum extent of ground floor coverage but in the basement water closet and bathroom shall not be permitted.

(vi) Ledge, Loft and

Mezzanine floor

Ledge, Loft and mezzanine floor shall be permitted within the building subject to the restrictions above as well as the restrictions stipulated in the definition given in Clause-II of Zoning Regulations of Development Plan.

(vii) Services, water supply and drainage

- a) Good potable water supply should be available in the farm for human consumption in case farm house is built.
- b) Open sanitary drains or covered drains to be provided to clean the sheds in case of dairy farms, Drains are to be provided for carrying rain water in case of all buildings.
- Septic tank to be provided for disposal of human and animals waste as per provisions of the Rules.
- d) The distance between the septic and open well or tubewell shall be as provided in the Rules.
- (viii) The owner shall be permitted to construct boundary wall around the main dwelling unit and ancillary portion thereof and around remaining area of farm barbed wire fencing shall be allowed.
- (ix) The CLU permissions for setting up of farmhouse shall be considered in the area other than over exploited or critical areas as declared by Central Ground Water Board:

Provided that Government may amend the minimum size of the farm house for any schemes sponsored by the State Government/State agency for the proper utilization of the agriculture zone.

# XVII Setting up of communication towers:-

Permission of Mobile Towers within the Controlled area shall be granted as per the policy dated 10th March, 2015 as amended from time to time;

# XVIII Safety against Seismic Hazards:-

As the Development Plan area falls in Seismic zone as per seismic zone map of Indian Standard IS 1893 and hence is considered as High Risk Zone. In order to take care of the same "the whole urban development shall be checked for safety against an intensity "VII" probability of occurrence and upgraded for required seismic resistance in buildings and infrastructure as found necessary".

# XIX Relaxation of Development Plan:-

Government may in case of hardship or with a view to save any structure constructed before the material date, relax any of the provisions of the Development Plan on principles of equity and justice on payment of such development charges and on such other conditions as it may deem fit to impose.

	Appendix – A						
-		Classificatio	n of Land uses				
Main	Sub	Main	Sub				
Code	Code	Group	Group				
400		Transport & Comm	unication				
	420		Roads, Road Transport Depots and Parking areas.				
		<b>Public Utilities</b>					
	510		Water Supply installation				
			Including treatment plants				
	520		Drainage and Sanitary				
			Installations including				
	520		Disposal works				
	530		Electric Power Plants, Sub Station etc.				
<b>7</b> 00	550	0 0	Solid waste disposal work				
700	720	Open Spaces	Ct. I'. N. C. 1				
	720 730		Stadiums, Play Grounds				
	730		Other Recreational Uses				
	750		Fuel Filling Stations and Bus Queue Shelters				
800	0.40	Agricultural Zone					
	840		Grazing and land pastures				
	850		Reserved for protected forest				
900		Special Zone	Special zone shall include recreational,				
			entertainment, Government offices, commercial, group				
			housing and institutional uses.				
1000		Restricted Zone	Beautification and Environment				
			Improvement Works, temple, museum, rest house &				
			police post.				

#### Appendix B

#### I Commercial zone

- (i) Retail Trade.
- (ii) Wholesale Trade.
- (iii) Warehouses and storages.
- (iv) Commercial offices and banks.
- (v) Restaurant and Transient Boarding Houses including public assistance institutions providing residential accommodation like Dharamshala, Tourist House etc.
- (vi) Cinemas, Hotels, Motels and other places of public assembly like theatres, club, Dramatic Club, etc. run on commercial basis.
- (vii) Professional establishments.
- (viii) Residences on the first and higher floors.
- (ix) Local service industry.
- (x) Public utility buildings.
- (xi) Petrol filling stations and service garages.
- (xii) Loading and unloading yards.
- (xiii) Parking spaces, bus stops, taxis, tonga and rickshaw stand.
- (xiv) Town parks.
- (xv) Communication Towers
- (xvi) Any other use, which the Government may in public interest decide

# II Transport and communication zone

- (i) Railway yards, railway station and siding
- (ii) Transport Nagar, Roads and Transport depots and parking areas
- (iii) Airports and Air Stations
- (iv) Telegraph offices and Telephone exchange
- (v) Broadcasting stations
- (vi) Televisions station
- (vii) Agricultural, horticulture and nurseries at approved sites and places
- (viii) Petrol filling stations and service garages
- (ix) Parking spaces ,bus stop-shelters, taxi, Tonga and rickshaw stands
- (x) Communications Towers
- (xi) Warehouses up to a maximum limit of 5% of the total area of the sector

#### **III Public utilities**

- (i) Water supply installations including treatment plants.
- (ii) Drainage and Sanitary installations, Disposal works.
- (iii) Electric Power plant and sub-station including grid sub-station.
- (iv) Gas installations and Gas works.
- (v) Solid waste disposal work.

#### IV Public and semi public uses zone

- (i) Government offices, Government Administration centres, secretariats and police station
- (ii) Educational, cultural and religious institutions
- (iii) Medical health institutions
- (iv) Civic/cultural and social institutions like theatres, opera houses etc. of predominantly non-commercial nature
- (v) Land belonging to Defence
- (vi) Dhabas, Restaurants as under: -

( * 1 )	Diabas, Restaurants as under.							
Sr.	Name of	Area		No. of	Commercial	Maximum	Floor	
No.	Facility	Mini	Maxi	facilities	component	Ground	Area	
		mum	mum	in a sector		Coverage	Ratio	
1	Dhabas	500	1000	2	50 sq. m	50 %	0.50	
		sq. m	sq. m					
2	Restaurants	1000	2000	2	10 %	30 %	1.50	
		sq. m	sq. m					

As required for the local needs of major use and needs of the town at site approved by the Director in the sector/ colony plan and as per the policy/ parameters decided by the Government.

At sites earmarked in the sector plan.

At sites earmarked in the sector plan.

At sites earmarked in the sector plan.

- (vii) Communication Towers
- (viii) Any other use, which the Government may in public interest decide

#### V Open spaces

- (i) Sports ground, stadium and play grounds
- (ii) Parks and green belts
- (iii) Cemetreies crematories etc.
- (iv) Motor fuel filling stations, bus queue shelter along roads with the permission of Director
- (v) Public utility services like electric grid station, transmission lines, communication lines, water supply lines, sewerage lines, drainage lines in the green belts along the scheduled roads and major roads.
- (vi) Water bodies/lakes /water recharge zone.
- (vii) Communication Towers
- (viii) Any other use, which the Government may in public interest decide.

#### VI Uses strictly prohibited:

Storages of petroleum and other inflammable material without proper license.

# VII Agriculture zone

- (i) Agricultural, Horticultural, dairy and poultry farming.
- (ii) Village houses within Abadi-deh
- (iii) Farm houses outside abadi-deh subject to restriction as laid down in zoning regulation XIX
- (iv) Afforestation development of any of the part for recreation
- (v) Expansion of existing village contiguous to abadi-deh if undertaken as a project approved or sponsored by the Central Government or State Government.
- (vi) Milk chilling station and pasteurisation plant
- (vii) Bus Stand and Railway Station
- (viii) Air ports with necessary buildings
- (ix) Wireless stations
- (x) Grain godowns, storage space at sites approved by the Director
- (xi) Weather stations
- (xii) Land drainage and irrigation, hydroelectric works and tubewell for irrigation
- (xiii) Telephone and electric transmission lines and poles
- (xiv) Mining and extraction operations including lime and brick kilns, stones, quarries and crushing subject to the rules and at approved site
- (xv) Cremation and burial grounds
- (xvi) Petrol filling station and service garages
- (xvii) Hydro electric/thermal power plant sub-station
- (xviii) Liquid Petroleum Gas storage godowns with the approval of the Director
- (xix) (a) Non Polluting industries registered as Rural Industry Scheme/Small Scale Industrial units outside the restricted belt around defence installations as applicable for such installation if any, subject to one of the following conditions:-
  - (i) Located within half kilometer belt encircling the existing village Abadideh and approachable from public road/rasta other than scheduled road, National Highway and State Highway.
  - (ii) On Public road/rasta not less than 30 feet wide (other than scheduled roads, National Highway and State Highway) outside the half kilometer zone referred to in (i) above upto a depth of 100 metres along the approach road.
  - (b) Non-Polluting Medium and Large Scale Agro Based industries on public roads/revenue rasta not less than 30 feet wide other than scheduled roads. National Highway and State Highway.

The site should not fall within restricted belt notified under the 'Works of Defence Act, 1903' around Defence installations, if any.

At sites approved by Director, Town and Country Planning, Haryana.

As approved by Director, Town and Country Planning Department, Haryana and as per the policy parameters decided by the Government.

(xx) Dhabas, Small Restaurants, Motels, Resort and Amusement Park/ Theme Park along National Highway / Scheduled Roads in the area outside restricted/ green belt as under:-

Sr.No.	Permissible	A	rea	Commercial	Maximum	Floor
	Activity	Minimum	Maximum	Component	Ground Coverag	Area Ratio
1	Dhabas	1000 square meters	1 acre	50 sqmt.	40%	0.40
2	Restaurant	2000 square meters	1 acre	15 %	30%	1.50
3	Motel with banquet facilities	2.5 acres	5 acres	15%	30%	1.50
4	Resort	4 acres	10 acres	15%	30%	1.50
5	Amusement Park/Theme Park	2.5 acres	10 acres	15%	30%	0.50

Provided the access permission is obtained from National Highway Authority of India if the site is located on National Highway and from Executive Engineer, Public Works Department (Building and Roads) if the site is located on scheduled road.

(ix) Service charge and Sale/ display Centre-cum-Service Garage

	Name of	1		Commercial		Floor	Approach	Height
	Facilities	Minimum	Maximum	Component	Ground Coverage	Area ratio	Road	
1	Service Garag	1/2	1	Nil	60%	1.25	Minimum 18 metres or service road along sector road	18 metres
2	Sale/display Centre-cum- service garage	1/2	2	10% of permissible Floor Area Ratio	60%	1.25	Minimum 18 metres or service road along sector road	18 metres

- the Go
- The fee and charges on commercial component shall be levied on the commercial rates.
- Existing/already CLU granted service garages shall be considered for grant of permission for sale/display centre subject to fulfillment of the above norms.

#### (xxi) Banquet Hall:


Permissible Zone	Agriculture
Approach	1. Minimum width of the approach road must be 18 metres.
	2. The access permission is required from XEN, PWD (B&R) if the site is located on scheduled road.
	3. Approach from National Highways can be considered, if the site fulfills minimum distance norms from intersection/access and is located on minimum 7 metres wide service road or the applicant submits prior permission of access from NHAI.
Area Required	Minimum area :- 2.5 acres
	Maximum area :- 5.00 acres
FAR	0.5
Ground Coverage	30%

As approved by
Director, Town and
Country
Planning
Department, Haryana
and as per policy/
parameters decided by
the Government.

Conversion Charges	50% of the rates prescribed for commercial use
Permissible Ancillary uses within FAR	10% of the allowed FAR for Gift shop, STD Booth, Toy Centres and flowers shops etc.
Parking	Minimum 25% of the site area

- (xxii) MicrowaveTowers/Stations, Seismic Centres and Telecommunication Centres
- (xxiii) Communication Towers
- (xxiv) Ready Mix Concrete Plants, Wet mix plants, Hot Mix Plants connected with the projects for which contract or work is assigned by Government or Government agency and to be set up on short term basis.
- (xxv) Any other use, which Government may in Public Interest, decide.

P. RAGHAVENDRA RAO, Additional Chief Secretary to Government Haryana, Town and Country Planning Department.



#### HARYANA GOVERNMENT

#### WOMEN AND CHILD DEVELOPMENT DEPARTMENT

#### **Notification**

The 24-08-2015

**No. 852** SW(3)2015.— In order to implement "Aapki Beti Hamari Beti" Scheme, the Governor of Haryana is pleased to issue following operational guidelines in the state of Haryana. These guidelines shall come into force w.e.f. 22th January, 2015.

#### 1. Aim:

The aim of this scheme is to improve child sex ratio and to ensure survival, proper health and promote education of girls in the state. Every girl child has a right to be born and have access to education in order to develop her potential.

#### 2. Coverage:

The Aapki Beti Hamari Beti Scheme shall be implemented in both rural and urban areas of the state, covering 1st girl child born in the families belonging to Schedule Caste, and all Below Poverty Line (BPL) and, 2nd /twin/multiple girls born on or after 22nd January, 2015 in any family in the State of Haryana satisfying the eligibility criteria. The LADLI scheme is merged into Aapki Beti Hamari Beti Scheme and 2nd /twin/multiple girls born on or before 21st January, 2015 in any family in the State of Haryana, satisfying the eligibility criteria of Scheme, will be paid benefit as per the rules of erstwhile LADLI Scheme.

#### 3. Eligibility Criteria:

The following will be the eligibility criteria for beneficiaries under the scheme:-

- (a) All Scheduled Caste families whose first girl child is born on or after 22nd January 2015shall be eligible to receive one time grant of rupees Twenty One thousand (Rs. 21,000/-) only.
- (b) All Below Poverty Line (BPL) families whose first girl child is born on or after 22nd January 2015 shall be eligible to receive one time grant of rupees Twenty One thousand (Rs. 21,000/-) only.
- (c) All families whose second girl child is born on or after 22ndJanuary 2015, will receive one time grant of rupees Twenty One thousand (Rs. 21,000/-) irrespective of their caste, creed, religion, income and number of sons.
- (d) In cases, twin/multiple girls are born on or after 22nd January 2015, will receive one time grant of rupees Twenty One thousand (Rs. 21,000/-) only per girl child in any family satisfying the eligibility conditions.
- (e) All families whose second girl child is born on or before 21st January 2015, will receive Rs. 5000/- girl child per annum for five years irrespective of their caste, creed, religion, income and number of sons. (This is applicable for those cases who were eligible for benefit under Ladli scheme).
- (f) In cases, when twin/multiple girls are born on or before 21stJanuary, 2015will receive Rs. 2500/- per girl child per annum for five years irrespective of their caste, creed, religion, income and number of sons in any family of the State of Haryana satisfying the eligibility conditions. (This is applicable for those cases who were eligible for benefit under Ladli scheme).
- (g) All parents resident of Haryana or having Haryana domicile and at least one of the parents along with the girl child should be residing in the Haryana.
- (h) The pregnant women should be registered at the nearest Anganwadi Centre or with the Health Department.
- (i) The birth of all girl children shall be registered.
- (j) The girl child shall have Aadhar number. However at the time of enrolment, Aadhar number of the parents is also accepted.
- (k) The parents should ensure proper and timely immunization of the girl children and immunization record (as per age of the girl children) should be attached with the application form.
- (1) Beneficiary should be enrolled in Anganwadi Centre as per their age.

#### 4. Financial Assistance:

Keeping in view the aims of the Scheme the Government will provide benefit/financial assistance to each girl child beneficiary. This will be provided in the following manner:-

- (a) All Scheduled Caste families whose first girl child is born on or after 22nd January 2015 shall be eligible to receive one time grant of rupees Twenty One thousand (Rs. 21,000/-) only.
- (b) All Below Poverty Line (BPL) families whose first girl child is born on or after 22nd January 2015 shall be eligible to receive one time grant of rupees Twenty One thousand (Rs. 21,000/-) only.
- (c) All families whose second girl child is born on or after 22ndJanuary 2015, will receive Rs. 21000/- (One Time) irrespective of their caste, creed, religion, income and number of sons.
- (d) In special cases, when twin/multiple girls are born on or after 22nd January, 2015 will receive Rs. 21000/- (One Time) per girl child in any family of the State of Haryana satisfying the eligibility conditions.
- (e) All families whose second girl child is born on or before 21st January 2015, will receive Rs. 5000/- girl child per annum for five years irrespective of their caste, creed, religion, income and number of sons. (This is applicable for those cases who were eligible for benefit under Ladli scheme).
- (f) In special cases, when twin/multiple girls are born on or before 21st January, 2015 will receive Rs. 2500/- per girl child per annum for five years irrespective of their caste, creed, religion, income and number of sons in any family of the State of Haryana satisfying the eligibility conditions. (This is applicable for those cases who were eligible for benefit under Ladli scheme).
- (g) The money shall be released within one month on submission of completed application of beneficiary through her mother/father/guardian.
- (h) The money is to be invested with LIC of India under the Scheme 'Aapki Beti Hamari Beti' in the name of girl child beneficiary through her mother. In case, mother is not alive then the money would be deposited in the name of beneficiary girl child through father. If both the parents are not alive then this money would be deposited in the name of beneficiary girl child through her guardian.
- (i) In case of death of beneficiary before 18 years of age, her enrolment as a beneficiary under the Scheme Aapki Beti Hamari Beti, would be cancelled with immediate effect and funds invested against this enrolment would be taken back from Scheme Aapki Beti Hamari Beti with interest and deposited in the receipt Head of the Department.
- (j) In case the applicant is unable to submit application Performa within time then maximum limit for submission of Performa will be just one year after the birth of beneficiary.

# 5. Scrutiny of Prospective beneficiaries:

The verification procedure in respect of beneficiaries shall be made by the ICDS Staff of Women and Child Development in both the Rural and Urban areas covered under ICDS Scheme. However, in the Non ICDS area, the verification of beneficiaries shall be made by the Health Staff of Civil Surgeon of concerned district.

# 6. Procedure for applying under scheme:

- (a) This scheme shall be implemented through Women and Child Development Department, Haryana.
- (b) The application forms will be available free of cost from the Anganwadi Centre or can be downloaded from the website (www.wcdhry.gov.in) of the Department.
- (c) The duly filled form along with the self-attested copy of the birth certificate & immunization card of the beneficiary and Aadhar number of child or of the parents shall be deposited with the Anganwadi Worker/Health Staff.
- (d) The Anganwadi worker/Health Staff shall submit the same to the Circle Supervisor/Medical Officer or to the Women and Child Development Project Officer/Civil Surgeon.
- (e) The Women and Child Development Project Officer/Civil Surgeon will forward the cases to the District Programme Officer of the concerned district, who will sanction the amount as per the eligibility of the beneficiaries and would deposit the said amount via Aadhar number linked with bank account of Life Insurance Corporation of India for investment in the name of the beneficiary.
- (f) Employees of Haryana Government, but residing at Chandigarh and Delhi can apply to District Programme Officer Panchkula and District Programme Officer Gurgaon respectively.

#### 7. Procedure for Sanction of Financial benefit:

In ICDS scheme in Rural and Urban areas, the respective Women & Child Development Project Officer shall send the cases to District Programme Officer and in Non ICDS urban areas, the Civil Surgeon of the district shall send the cases to concerned District Programme Officer for sanction of financial assistance to the eligible beneficiary.

#### 8. Mode of making Investment and Financial Assistance to the beneficiary girl child:

- (a) The mother/ father/guardian of the eligible girl child beneficiary should apply in the prescribed form along with relevant documents as prescribed by Women and Child Development Department, Haryana through Anganwadi Worker/Supervisor/Health Staff of the concerned area.
- (b) The Women & Child Development Project Officer in ICDS area and Civil Surgeons in Non ICDS areas will recommend the cases to the District Programme Officers of the concerned district who would sanction the amount and deposit in the account of LIC of India for investment in the name of beneficiary girl child.
- (c) The LADLI Scheme is merged into Aapki Beti Hamari Beti Scheme.

#### 9. Issue of Membership Certificate to the beneficiary girl child:

Life Insurance Corporation of India shall issue a Membership Certificate in favour of each beneficiary enrolled with them. The said membership certificate shall be given to the concerned District Programme Officer for onward delivery to the parents/guardian of the concerned beneficiary.

#### 10. Withdrawal of Benefit:

- (a) The benefit sanctioned under the scheme shall be withdrawn by the competent authority at any stage, if it is found that it was sanctioned incorrectly or received by providing false information/fabricated documents.
- (b) In case of wrong information, deliberately given by the applicant, he/she shall be liable for prosecution as per law.
- (c) The investment made in the shape of membership certificate under this scheme shall not be liable for attachment under any law.
- (d) If the beneficiary dies after attaining the age of 18 years then parents of beneficiary will be eligible for receiving benefit.
- (e) The beneficiary would not be eligible for the benefit under the scheme in case she gets married before the age of 18 years.

#### 11. Monitoring of Scheme:

Monitoring of this scheme shall be done at the level of Women and Child Development Department, Haryana and also by 3rd Party audit, as decided by state Government from time to time.

# 12. Change of address:

It shall be obligatory for the parents/guardian of the girl children to intimate any change of address to the Women and Child Development Project Officer/ District Programme Officer and Civil Surgeon concerned.

# 13. Eligibility to encash Membership Certificate:

In order to obtain the maturity value of the investment in Membership Certificate at the time of applying the beneficiary girl must be:

- (a) 18 years of age.
- (b) Unmarried.

#### 14. Procedure to encash Membership Certificate:

The eligible girl along with her mother, father and guardian will apply on the prescribed proforma to the District Programme Officer, Who after ascertaining the eligibility shall hand over the Membership Certificate to the beneficiary.

#### 15. Drawing and Disbursing Officer of the Scheme:

The District Programme Officer of the district will be the Drawing and Disbursing Officer of this scheme. All the undisbursed amount shall be kept by the Programme Officer. A proper record of such amounts shall be kept in a separate register. The undisbursed amount shall be taken in the cashbook and the entire amount thus received, shall be adjusted by short drawal from the subsequent bill.

Receipt in the prescribed proforma shall be obtained from the beneficiary at the time of maturity of Membership Certificate. The same shall be kept by the District Programme Officer concerned, till the accounts have been audited by the Accountant General, Haryana.

- 16. The Director, Women and Child Development, Haryana shall be overall in charge of the "Aapki Beti Hamari Beti" scheme and necessary instructions in regard to its proper enforcement and accounting procedure shall be issued by her from time to time. At the field level District Programme Officer shall be overall incharge of the implementation of the scheme in the district.
- 17. The expenditure on the implementation of the "Aapki Beti Hamari Beti" scheme 2015 including the money of Membership Certificate or any other expenditure on disbursement of financial assistance to the beneficiaries shall be debitable to the head of the account as prescribed by Government from time to time.

Chandigarh: The 19th August, 2015. DR. AVTAR SINGH, Principal Secretary to Government Haryana, Women& Child Development Department.

#### हरियाणा सरकार

विकास तथा पंचायत विभाग

# शुद्धि पत्र

दिनांक 20 अगस्त, 2015

संख्या ई0सी0ए0—5—2015/788.— हरियाणा सरकार राजपत्र (असाधारण) दिनांक 10 दिसम्बर, 2014 में प्रकाशित हरियाणा सरकार, विकास तथा पंचायत विभाग आदेश संख्या ई0सी0ए0—5—2014/609 में, पृष्ठ संख्या 3892 पर रेवाड़ी के क्रम संख्या 40 में ग्राम पंचायत जीतपुरा ईस्तमुरार के सम्मुख खाना नं0 3, 4, 5, 6, 7, तथा 8 में अंक 7, 3, 1, 1, 1 तथा 3 के स्थान पर अंक 11, 4, 2, 1, 1 तथा 5 पढ़ा जाये।

राम निवास , अतिरिक्त मुख्य सचिव, हरियाणा सरकार, विकास तथा पंचायत विभाग।

# HARYANA GOVERNMENT

# ADMINISTRATIVE REFORMS DEPARTMENT (CENTRAL COMMITTE OF EXAMINATIONS)

#### **DATE-SHEET**

#### **Notification**

The 24th August, 2015

No. 1/4/2015-1Exam.—The next departmental examinations of various departments of Haryana Government are going to be held in the month of October, 2015 on the dates and time specified below. The examinations will take place in Lajpat Rai Bhawan, Sector-15, Chandigarh. For details of the various examinations the intending examinees are referred to the relevant departmental rules:-

Dates and hours	Assistant commissioners, Extra Assistant Commissioners and the candidates	I.P.S. officers	Civil-Judges and candidates for the posts of Civil- Judges	Tehsildars	Forest Department	Agriculture/ Horticulture Department	Excise and Taxation Department
	for the post of E.A.Cs.						
1	2	3	4	5	6	7	8
5-10-2015 (M) 10.00 a.m. to 1.00 p.m.	Criminal Law, 1st Paper			Criminal Law, 1st Paper	Forest Law		
(E) 2.00 p.m. to 5.00 p.m.	Civil Law		Accounts	Civil Law	Land Revenue		
6-10-2015 (M) 10.00 a.m. to 1.00 p.m.	Criminal Law 2 <sup>nd</sup> Paper		Civil Law	Criminal Law 2 <sup>nd</sup> Paper	Procedure and Accounts		
(E) 2.00 p.m. to 5.00 p.m.	Financial Rules		Criminal Law	Financial Rules	Hindi		
7-10-2015 (M) 10.00 a.m. to 1.00 p.m.	Criminal Law, 3 <sup>rd</sup> Paper (including Jails)		Revenue Law, 1st Paper	Criminal Law, 3rd Paper (excluding Jails)			
(E) 2.00 p.m. to 5.00 p.m.	Revenue Law, 1st Paper			Revenue Law, 1st Paper			
8-10-2015 (M) 10.00 a.m. to 1.00 p.m.	Local Funds		Revenue Law, 2 <sup>nd</sup> Paper	Local Funds			
(E) 2.00 p.m. to 5.00 p.m.	Revenue Law, 2 <sup>nd</sup> Paper		Constitutional Law	Revenue Law, 2 <sup>nd</sup> Paper			
9-10-2015 (M) 10.00 a.m. to 1.00 p.m.	Language (Hindi)	Language (Hindi)		Patwari's Mensuration			
(E) 2.00 p.m. to 5.00 p.m.				Urdu		Accounts	
14-10-2015 (M) 10.00 a.m. to 1.00 p.m.							Subject-1 (Law of Crimes)
(E) 2.00 p.m. to 5.00 p.m.							Subject-II (Excise Law)
15-10-2015 (M) 10.00 a.m. to 1.00 p.m.							Subject-III (Allied Taxes)
(E) 2.00 p.m. to 5.00 p.m.							Subject-IV (Sales Tax Law)
16-10-2015 (M) 10.00 a.m. to 1.00 p.m.							Subject-V (Book Keeping)
(E) 2.00 p.m. to 5.00 p.m.							Subject-VI (Computer Operation)

Dates and hours	*Animal	Fisheries	Prisons	Co-operative	Block	SDO's	Wild Life	Elections
	Husbandry and	Department	Department	Department	Development	Panchayati Raj	Preservation	Department
	Dairying				and	Deptt.	Department	
	Department.				Panchayats	(Enginering		
	40	11	12	40	Officers	Groups)	16	47
9 5-10-2015 (M) 10.00 a.m. to	10 Accounts	Accounts	12	13	14 Group-I	15	Account &	17
1.00 p.m.	Accounts	Accounts			Paper-A		Departmental	
1.00 p.m.					r aper-A		Rules	
(E) 2.00 p.m. to	*Departmental	*Departmental				I P.W.D.		
5.00 p.m.	Rules	Rules				Specifications		
6-10-2015 (M) 10.00 a.m. to					Group-I			
1.00 p.m.					Paper-B			
(F) 0.00 m m 4a				A		II Danies		
(E) 2.00 p.m. to 5.00 p.m.				Accounts		II Design		
5.00 p.iii.								
7-10-2015 (M) 10.00 a.m. to			Subject-I		Groupt-II			
` 1.00 p.m.			(Punjab jails		(Budget and			
			manual without		Accounts)			
			appendices)					
			Cultinat II					
(E) 2.00 p.m. to			Subject-II (Punjab Jails			III Manual of		Election
(E) 2.00 p.m. to 5.00 p.m.			Manual with			orders.		Laws (For
3.00 p.m.			appendices and			Accounts and		Assistants
			other matters			office		or Election
						procedure		Kanungos)
								,
8-10-2015 (M) 10.00 a.m. to			Subject-III		Group-III			
1.00 p.m.			(Criminal Law)		(Statutory Acts			
1.00 p.m.			(Ommar Law)		and Rules			
			Subject-IV					
(E) 2.00 p.m. to			(Financial			IV Maintenance		
5.00 p.m.			Rules)			of T&P Earth		
						Moving and Road making		
						Machinery		
9-10-2015 (M) 10.00 a.m. to			Subject-V					Administrati
1.00 p.m.			(Language					ve/
			Hindi)					Accounts
								Rules (For
								Assistants
								or Elections Kanungos
(E) 2.00 p.m. to						Estimating		Nationgus
5.00 p.m.						Lounding		
0.00 p.iii.								Election
								Law (For
								JSS/ST,
								Clerks or
								Moharrirs)

- 1. \* Officers of the Haryana Veterinary Service, Class-I, are not required to appear in this Paper.
- 2. Those who intend to appear in the examination should immediately apply to their Head of Deptt./Administrative Secretary as the case may be with particulars in the form below by 15th September, 2015. No direct application will be entertained by the Central Committee of Examinations.
  - Form → Name of examinee Subject to groups in which the candidate will appear No.s of chance(s) already availed by examinees Signature of Examinee
- 3. The intending examinees who are prevented from appearing in the examination for any reasons should give timely notice to the Secretary, Central Committee of Examinations of their inability to appear

ANURAG RASTOGI, Principal Secretary to Government Haryana, Co-ordination Department-cum-Secretary, Central Committee of Examinations, Haryana.